

CONCRETE AND CONSTRUCTIONAL ENGINEERING

THE UNIVERSITY
OF MICHIGAN

INCLUDING PRESTRESSED CONCRETE

THE UNIVERSITY
OF MICHIGAN

JAN 13 1960

JAN 13 1960

ENGINEERING
DECEMBER 1959



ENGINEERING
LIBRARY

VOL. LIV. NO. 12

FIFTY-FOURTH YEAR OF PUBLICATION

PRICE 2s.

ANNUAL SUBSCRIPTION 24s. POST FREE. \$3.90 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
Increasing Productivity	393
Design of Chimneys for Resistance to Weight and Wind By Leslie Turner	395
Elevated Road at Chiswick, London	403
Book Reviews	407
Prestressed Bridge over the River Medway	408
UNESCO Headquarters in Paris	411
Bridges on the London-Birmingham Motorway	413
Accelerated Test for Cement	417
A Prestressed Precast Bunker	419

No. 625

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For Catalogue of "Concrete Series" books on
concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.

INDEX OF ADVERTISERS

	Page		Page
A.B. Mould & Construction Co. Ltd.	lii	LEEDS OIL & GREASE CO.	xxviii
ABELSON & CO. (ENGINEERS) LTD.	xlii	LENSCRETE LTD.	li
A.C.E. MACHINERY LTD.	—	LILLINGTON, GEGGE, & CO. LTD.	xvi
ACROW (ENGINEERS) LTD.	—	LIND, PETER, & CO. LTD.	vii
ALLAM, E. P., & CO. LTD.	lvii		
ANGLIAN BUILDING PRODUCTS LTD.	—	McCALL & CO. (SHEFFIELD) LTD.	xxxix
AVON MANUFACTURING (WARWICK) LTD.	—	McCALLS MACALLOY LTD.	xxviii
		McKINNEY FOUNDATIONS LTD.	xv
BAMBERGERS LTD.	—	MARLEY CONCRETE LTD.	viii
BERRY'S ENGINEERING CO.	—	MAY & BUTCHER LTD.	—
BOULDER EQUIPMENT LTD.	—	MICANITE & INSULATORS CO. LTD.	—
BOYER, WM., & SONS LTD.	xxxvi	MILBANK FLOORS LTD.	xxx
BRAITHWAITE & CO., ENGINEERS, LTD.	—	MILLARS' MACHINERY CO. LTD.	xli
B.R.C. ENGINEERING CO. LTD.	lxviii	MILLS SCAFFOLD CO. LTD.	xxvi, xxvii
BRETT, ROBERT, & SONS LTD.	—	MONK, A., & CO. LTD.	xv
BRITISH STEEL PILING CO. LTD.	xxxv	MORAN, WHITLEY, & CO. LTD.	—
BRITISH VISQUEEN LTD.	xxiii	MULCASTER, WM., & CO. (CONTRACTORS) LTD.	xlii
BYRD, A. A., & CO. LTD.	lix		
		OMNIA CONSTRUCTIONS LTD.	v
CAPLIN ENGINEERING CO. LTD.	xxxiv		
CEMENT MARKETING CO. LTD.	xx	PASHLEY & TRICKETT LTD.	—
CEMENT & STEEL LTD.	vi	PIERHEAD LTD.	lx
CEMENTATION CO. LTD.	—	PORTASALO LTD.	lviii
CHAPMAN, H. W., LTD.	—	PRESTRESSED SALES LTD.	—
CHEETHAM, ALEX. J., LTD.	xli	PRIEST, B., & SONS LTD.	xxxiv
CHRISTIANI & NIELSEN LTD.	—	PRODUCTION CHEMICALS (ROCHDALE) LTD.	—
CLIFFER MANUFACTURING CO. LTD.	—	P.S.C. EQUIPMENT LTD.	x, xi
COLCRETE LTD.	xxii	PYNFORD LTD.	—
COLVILLES LTD.	—		
CONCRETE PILING LTD.	—	RANALAH STEEL MOULDS LTD.	xlix
CONCRETE PROOFING CO. LTD.	xxxviii	RAWPLUG CO. LTD.	xxxiii
CONCRETE PUMP CO. LTD.	xvii	RICE & SON LTD.	—
CONCRETE SERVICES LTD.	xxi	RICHARDS, W., & SONS LTD.	—
CONVEYBEARE & CO. LTD.	xxviii	ROAD MACHINES (DRAYTON) LTD.	—
COWLIN, WILLIAM, & SON LTD.	—	ROVER CAR CO. LTD.	xli
		RUSH & TOMPKINS LTD.	liii
D.A. MODELS LTD.	iv	RYLANDS BROTHERS LTD.	xlv
DAVIDSON'S PAPER SALES LTD.	—		
DICKENS, STUART B., LTD.	xxxi	St. IVES SAND & GRAVEL CO. LTD.	—
DORMAN LONG (STEEL) LTD.	—	SAMUEL & SON LTD.	liv
DOUGLAS, ROBERT M. (CONTRACTORS) LTD.	—	SEALOCRETE PRODUCTS LTD.	—
		SHOCKCRETE PRODUCTS LTD.	xxxi
EVODE LTD.	—	SIMON-CARVES LTD.	—
EXPANDITE LTD.	—	SIMPLEX CONCRETE PILES LTD.	xli
		SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.	—
FEB (GREAT BRITAIN) LTD.	iii	SPENCER WIRE CO. LTD.	—
FLEXIBLE DRIVE & TOOL CO. LTD.	xl	STELMO LTD.	lxii
FORD MOTOR CO. LTD.	xxxvii	STENT PRECAST CONCRETE LTD.	—
FRANKPILE LTD.	xxix	STIC B PAINT SALES LTD.	—
		STONE COURT BALLAST CO. LTD.	—
GADD, GEORGE, & CO. LTD.	—	STORER, WM. T., & CO. LTD.	xiii
G.K.N. REINFORCEMENTS LTD.	lxiii	STRESSING DEVELOPMENTS LTD.	lv
GLEESON, M. J. (CONTRACTORS) LTD.	xli	STUART'S GRANOLITHIC CO. LTD.	xl
GREENWOOD, GEORGE, & SONS	—		
GUNITE CONSTRUCTION CO. LTD.	li	TARMAC LTD.	ix
		TECHNICAL PAINT SERVICES	—
HALL & CO. LTD.	—	TELEHOIST LTD.	—
HALL & SONS (MINORIES) LTD.	—	TENTOR BAR CO. LTD.	lxvii
HILL, RICHARD, LTD.	xiv	TERRESEARCH LTD.	—
HILTON GRAVEL LTD.	—	TERSONS LTD.	—
HOLLAND & HANNEN AND CUBITTS (GT. BRITAIN) LTD.	xix	THAMES PLYWOOD MANUFACTURERS LTD.	lxviii
HOLMPRESS PILES LTD.	—	THOMAS & PRICE (TIMBER) LTD.	—
HOLST & CO. LTD.	—	T.P. POLYPLASTIC CONVERTERS LTD.	xxxi
HUNTLEY & SPARKS LTD.	xxxii	TRENT GRAVELS LTD.	lxvi
		TUNNEL PORTLAND CEMENT CO. LTD.	—
IMPERIAL CHEMICAL INDUSTRIES LTD.	—		
		VOLKMAN, O. A.	—
JOHNSON, RICHARD, & NEPHEW LTD.	xxiv		
JONES, T. C., & CO. LTD.	l	WALKER WRIGHT & CO. LTD.	—
JOY SULLIVAN LTD.	—	WATES LTD.	—
		WELBECK TRADING CO. LTD.	xxxvii
KERNER GREENWOOD & CO. LTD.	—	WELLSMAN BROS. LTD.	—
KING, J. A., & CO. LTD.	xlv	WESTWOOD, JOSEPH, & CO. LTD.	xlii
		WHITEHEAD IRON & STEEL CO. LTD.	—
LAFARGE ALUMINOUS CEMENT CO. LTD.	lxiii	WHITLEY MORAN & CO. LTD.	—
LAING, JOHN, & SON LTD.	—		
LAWS & SON (STAINES) LTD.	xxxvi	YORKSHIRE HENNEBIQUE CONTRACTING CO. LTD.	—
LEARY'S FIREBOARDS LTD.	—		

ge
m
li
vi
m

ix
m
v

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

—

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LIV, No. 12.

LONDON, DECEMBER, 1959.

Increasing Productivity.

It is commonly said that when labour was cheap there was no harm in using it extravagantly, and that the need to save labour becomes desirable or necessary only as its cost increases. This argument fails to recognise that the words cheap and dear have no meaning unless they are related to other prices. When a man was paid a shilling an hour and could provide a dinner for his family for eight pence, and his employer paid the then price for a motor-car, the cost of labour and goods was relatively the same as it is when a man is paid six shillings an hour and can provide a dinner for his family for four shillings, and the employer pays six times as much for a car. Then, as now, builders built for profit and endeavoured to get the best value for the money they paid in wages. The difference is that men now work fewer hours a year and builders need more profit so that a reasonable reward will remain after taxation, and all need more to keep pace with inflation. The result is that employers have to think harder, to devise new ways of getting more production by the use of machinery, to eliminate unnecessary work, to avoid men being idle through no fault of their own, and to pay bonuses to encourage men to work harder. Some of these means of increasing production, particularly payment by piecework, have been in use for centuries. The application of all these means has now been intensified.

This is only partly shown in a bulletin entitled "Better Methods in the Building Trades" * which purports to describe methods of reducing costs adopted by eight builders, one sub-contractor, and one builders' merchant. In these cases work study departments have been set up or work study specialists employed, and their recommendations have resulted in increasing production and in saving cost. Much of the twenty pages of text in the bulletin is devoted to laudatory remarks on the merits of work study and on the firms whose enterprise is described. There are also some examples of the methods by which greater production, and consequently lower costs, have been achieved. These are all so obvious that the only impression one gets in reading about them is of amazement that the state of affairs that has been remedied could have been allowed to exist. The praise that is lavished upon these firms for seeing that their men did not waste their time in such ridiculous ways reminds one of the different treatment meted out by a noble lord on hearing that a burglar had got into his castle: he sent for the butler and gave him a golden sovereign for catching the burglar and a week's

* Published by the British Productivity Council. Price 5s.

notice for allowing him to get in. The stupid ways in which men were found to be wasting time and materials are indicated in the following examples given in the bulletin.

Instead of erecting a working platform under the whole of a factory ceiling for the use of painters and electricians, platforms were erected for two bays only so that while men were working on one platform the other was being dismantled and re-erected. Production was increased by one-fifth by ensuring that bricklayers always had a supply of bricks and mortar on the scaffold. In a case where floor slabs of mixed sizes were delivered by lorry, the men unloaded the slabs much quicker than they were laid because the paviors had to sort out the slabs; the slabs were laid twice as fast when the unloaders, instead of standing idle, arranged the slabs in the order in which they were needed. By using a ladder instead of a staging two men were able to fix small plastic wall panels at a height of 30 ft. at the rate of three minutes each instead of twenty. A "work study engineer" discovered that the marking of glazing-bars could save much time on the site. Six carpenters fixing joinery queued to use one drill; when this was discovered three drills were supplied. On the same works skirting boards of various lengths were stored together and sorted by the carpenters—"those who were painstaking enough to search for the right lengths lost time; the others had to waste material cutting down excessively large pieces to size"—time and material were saved by storing the various sizes separately. A "work study man" pointed out that time could be saved if carpenters' benches were nearer to their work.

In a precast concrete shop a team of six men included two carpenters who generally worked part time only, and the work was arranged so that they could also do other work. Much time was spent in making and using small pieces of shuttering to form grooves at the tops of columns to receive the ends of precast beams, and in grouting these connections; a saving of 15 per cent. in the cost of shuttering was made by forming slots in the top of the column shutters to receive the ends of the beams, supporting the beams in these slots, and then concreting the columns. A saving was made in the erection of a multiple-story building by leaving a hole in each floor through which the centering and its supports could be passed for use on the floor above, instead of passing the material through doors and windows and hoisting it up outside the structure. Savings were made by using baseboard instead of plaster-board, and by supplying and fixing plaster-board instead of having the work done by a sub-contractor.

In all the cases mentioned in this bulletin it was found that the men co-operated willingly when it was explained to them that increased production would result in increased earnings, but it is not stated why the simple and obvious improvements could not have been made by the builder's own staff and without the extra cost of works study specialists and in some cases "site meetings every fortnight with military regularity". Indeed the bulletin will probably be most welcomed by those who contend that the building industry is so inefficient that it should be nationalised. It is tragic that this publication should be issued at a time when a really useful account could be written of the recent achievements of the building industry in reducing cost and construction time by the use of new plant, new processes, and new materials, in which it is doubtful if work study specialists had any part.

Design of Chimneys for Resistance to Weight and Wind.

By **LESLIE TURNER, B.Sc., M.I.C.E., PP.I.Struct.E.**

As in the case of most structures, the design of reinforced concrete chimneys is a matter of trial and error. The calculations are complicated further because the effects of differences and changes of temperature have to be considered and combined with those due to the weight of the chimney and the effect of wind. In the following a method using charts is described whereby the stresses due to weight and wind can be readily determined. The combination of these stresses with the stresses due to temperature has been described elsewhere.*

The height and internal dimensions of a chimney are determined from considerations of thermodynamics, experience, and probably the requirements of national and local authorities, and will be given to the designer by those responsible for the plant and process from which the chimney is required to conduct gases. The maximum temperature and chemical analyses of the gases entering at the flue must therefore be known. From these data the material of construction, the thickness, the method of construction, and the protection of the inner face of the concrete must first be determined. In the past some concrete chimneys have not been lined, or lined for only part of their height. This may be satisfactory for cool and inert gases, such as warm clean air, but it is not recommended for exhausts from boilers of any kind and certainly not from industrial plants.

In determining the thickness of the shaft it must be borne in mind that it must remain intact after periodical heating and cooling when it is out of use. A final consideration is whether the lining shall be free-standing, that is whether its whole weight shall be carried on its lowest course or whether it shall be supported at intervals throughout its height on corbels or brackets built monolithically with the shaft. In this case the thickness of the lining will be less at the bottom, but its weight will be carried by the concrete shaft.

When the height of the chimney is known, the outside diameter at any horizontal plane depends on the internal diameter required, the air-space (if any) between the shaft and the lining, and the thickness of the lining. A slight taper is desirable for the sake of the appearance of the chimney, but it may not be essential.

A tentative elevation should be drawn and divided into sections of height, usually about 20 ft. to 25 ft. in the case of tall chimneys, and the weight of the shaft, including any lining carried by that part of the shaft and the corbels on which it is supported, should be evaluated at each of these horizontal sections. Bending moments due to the wind at these sections must also be calculated, the average wind pressure on every trapezoidal area being multiplied by the distance from the horizontal section to the centroids of the areas above the section. Having determined the weight carried on each horizontal section and the bending moment due to the wind at each section, other requirements, such as the thickness of the shaft and the percentage of reinforcement, are assumed if they are not known. The stresses due to wind and weight are then calculated. If the difference in temperature through the wall of the shaft is considerable it may be

* "Reinforced Concrete Chimneys." By C. P. Taylor and Leslie Turner (Concrete Publications, Ltd.).




Fig. 1.

necessary for the maximum stress due to wind and weight to be not more than about half the compressive stress permissible in the concrete. The corresponding tensile stress in the reinforcement should be about one-tenth or less of the permissible stress in order that the final stresses, taking into account those due to temperature, do not exceed the permissible stresses. It is also inherent in the nature of the problem that the tensile stresses in the reinforcement cannot approach the ordinary working stresses, although some specifications quote such limiting stresses.

Analysis of Annular Sections.

The assumptions made in the analysis which follows are those for the ordinary elastic theory of reinforced concrete.

NOTATION.

- c_w , maximum compressive stress in concrete due to wind and weight only (lb. per square inch).
 J , thickness of shaft (in.).
 J_s , thickness of an imaginary steel shell of mean radius R having a cross-sectional area equal to the actual area of the vertical reinforcement bars (in.).
 M , moment of the wind about the section (in.-lb.).
 m , modular ratio.
 mc_w , maximum compressive stress in the vertical reinforcement due to wind and weight only (lb. per square inch).
 p , percentage of vertical reinforcement = $\frac{100J_s}{J}$; r = proportion of vertical reinforcement = $\frac{J_s}{J} = \frac{p}{100}$; total area of reinforcement = $2\pi RJ_s$ (sq. in.).

- R , mean radius of shaft (in.)
 t_w , maximum tensile stress in the vertical reinforcement due to wind and weight only (lb. per square inch).
 W , weight carried on the horizontal section (lb.).
 ρ , thickness of element of shaft.
 θ , angle defining position of element of shaft.
 α , half angle subtended by compressive zone of shaft.
 e , eccentricity $\left(= \frac{M}{W} \right)$ at any horizontal section.

BASIC FORMULÆ.—The analysis of an annular section proceeds as in the following.

Consider element $p \cdot d\rho \cdot d\theta$ of concrete shell.

$$\text{Stress in element} = \frac{\rho \cos \theta - R \cos \alpha}{R + \frac{\rho}{2} - R \cos \alpha} c_w.$$

$$\text{Total Compression in element} = \frac{\rho \cos \theta - R \cos \alpha}{R + \frac{\rho}{2} - R \cos \alpha} c_w p \cdot d\rho \cdot d\theta.$$

$$\text{Moment of element about N.A.} = \frac{(\rho \cos \theta - R \cos \alpha)^2}{R + \frac{\rho}{2} - R \cos \alpha} c_w p \cdot d\rho \cdot d\theta.$$

$$\therefore \text{Integrating from } \rho = R - \frac{1}{2} \text{ to } \rho = R + \frac{1}{2},$$

$$\begin{aligned} \text{Total Compression in element } d\theta &= \frac{c_w d\theta}{R + \frac{\rho}{2} - R \cos \alpha} \int_{R - \frac{1}{2}}^{R + \frac{1}{2}} (\rho^2 \cos \theta - \rho R \cos \alpha) d\rho \\ &= \frac{c_w d\theta}{R + \frac{\rho}{2} - R \cos \alpha} \left[(R^2 J + \frac{1}{12} J^3) \cos \theta - R^2 J \cos \alpha \right]. \end{aligned}$$

$$\begin{aligned} \text{Total moment of element } d\theta \text{ about N.A.} &= \frac{c_w d\theta}{R + \frac{\rho}{2} - R \cos \alpha} \int_{R - \frac{1}{2}}^{R + \frac{1}{2}} \rho (\rho \cos \theta - R \cos \alpha)^2 d\rho \\ &= \frac{c_w d\theta}{R + \frac{\rho}{2} - R \cos \alpha} \left[(R^3 J + \frac{R J^3}{4}) \cos^2 \theta - (2R^3 J + \frac{R J^3}{4}) \cos \theta \cos \alpha + R^3 J \cos^2 \alpha \right]. \end{aligned}$$

$$\text{Stress in steel at } \theta = m c_w \frac{R \cos \theta - R \cos \alpha}{R + \frac{\rho}{2} - R \cos \alpha}.$$

$$\therefore \text{Total force in steel in element } d\theta = \frac{J r m c_w}{R + \frac{\rho}{2} - R \cos \alpha} (R \cos \theta - R \cos \alpha) R d\theta.$$

$$\therefore \text{Moment of this force about N.A.} = \frac{J r m c_w}{R + \frac{\rho}{2} - R \cos \alpha} (R \cos \theta - R \cos \alpha)^2 R d\theta.$$

Integrating for concrete between 0 & α and for steel between 0 and π ,
 Total net compression in half shell

$$\begin{aligned} &= \frac{c_w}{R + \frac{\rho}{2} - R \cos \alpha} \int_0^\alpha \left[(R^2 J + \frac{J^3}{12}) \cos \theta - R^2 J \cos \alpha \right] d\theta + \frac{R^2 J r m c_w}{R + \frac{\rho}{2} - R \cos \alpha} \int_0^\pi (\cos \theta - \cos \alpha) d\theta \\ &= \frac{c_w}{R + \frac{\rho}{2} - R \cos \alpha} \left\{ (R^2 J + \frac{J^3}{12}) \sin \alpha - R^2 J \cos \alpha - R^2 J r m \pi \cos \alpha \right\}. \end{aligned}$$

Similarly total moment of internal forces in half shell about N A

$$= \frac{c_w}{R + \frac{1}{2} - R \cos \alpha} \int_0^{\pi} \left[(R^3 J + \frac{R J^3}{4}) \cos^2 \theta - (2 R^2 J + \frac{R J^3}{2}) \cos \theta \cos \alpha + R^3 J \cos^2 \alpha \right] d\theta$$

$$+ \frac{J r m c_w R^3}{R + \frac{1}{2} - R \cos \alpha} \int_0^{\pi} (\cos \theta - \cos \alpha)^2 d\theta$$

$$= \frac{c_w}{R + \frac{1}{2} - R \cos \alpha} \left[(R^3 J + \frac{R J^3}{4}) \left(\alpha + \frac{1}{2} \sin 2\alpha \right) - (2 R^2 J + \frac{R J^3}{2}) \sin \alpha \cos \alpha + R^3 J \alpha \cos^2 \alpha \right.$$

$$\left. + J r m R^3 \left(\frac{\pi}{2} + \pi \cos^2 \alpha \right) \right]$$

Let W = applied direct load; M = applied moment about centre line, $e = \frac{M}{W}$
Then applied moment about N A = $M - W R \cos \alpha$.

$$W = \frac{2 c_w}{R + \frac{1}{2} - R \cos \alpha} \left\{ (R^2 J + \frac{J^3}{12}) \sin \alpha - R^2 J \alpha \cos \alpha - R^2 J r m \pi \cos \alpha \right\}$$

$$\text{or } W = \frac{2 c_w R J}{1 + \frac{1}{2R} - \cos \alpha} \left\{ \left(1 + \frac{J^2}{12 R^2} \right) \sin \alpha - \alpha \cos \alpha - r m \pi \cos \alpha \right\}.$$

$$\text{Also } M - W R \cos \alpha = \frac{2 c_w R^2 J}{1 + \frac{1}{2R} - \cos \alpha} \left\{ \left(1 + \frac{J^2}{4 R^2} \right) \left(\alpha + \frac{1}{2} \sin 2\alpha \right) - \left(2 + \frac{J^2}{2 R^2} \right) \sin \alpha \cos \alpha \right.$$

$$\left. + \alpha \cos^2 \alpha + r m \left(\frac{\pi}{2} + \pi \cos^2 \alpha \right) \right\}.$$

$$\frac{M - W R \cos \alpha}{W} = \frac{R \left[\left(1 + \frac{J^2}{4 R^2} \right) \left(\alpha + \frac{1}{2} \sin 2\alpha \right) - \left(2 + \frac{J^2}{2 R^2} \right) \sin \alpha \cos \alpha + \alpha \cos^2 \alpha + r m \left(\frac{\pi}{2} + \pi \cos^2 \alpha \right) \right]}{\left(1 + \frac{J^2}{12 R^2} \right) \sin \alpha - \alpha \cos \alpha - r m \pi \cos \alpha}$$

$$= \frac{R \left[\left(1 + \frac{J^2}{4 R^2} \right) \frac{\alpha}{2} - \left(\frac{3}{2} + \frac{J^2}{24 R^2} \right) \sin \alpha \cos \alpha + \alpha \cos^2 \alpha + r m \left(\frac{\pi}{2} + \pi \cos^2 \alpha \right) \right]}{\left(1 + \frac{J^2}{12 R^2} \right) \sin \alpha - \alpha \cos \alpha - r m \pi \cos \alpha}$$

$$\left(1 + \frac{J^2}{4 R^2} \right) \frac{\alpha}{2} - \left(\frac{3}{2} + \frac{J^2}{24 R^2} \right) \sin \alpha \cos \alpha + \alpha \cos^2 \alpha + r m \left(\frac{\pi}{2} + \pi \cos^2 \alpha \right)$$

$$\text{Then } \frac{e}{R} - \cos \alpha = \frac{\left(1 + \frac{J^2}{12 R^2} \right) \sin \alpha - \alpha \cos \alpha - r m \pi \cos \alpha}{\left(1 + \frac{J^2}{4 R^2} \right) \frac{\alpha}{2} - \left(\frac{3}{2} + \frac{J^2}{24 R^2} \right) \sin \alpha \cos \alpha + \alpha \cos^2 \alpha + r m \left(\frac{\pi}{2} + \pi \cos^2 \alpha \right)}$$

$$\therefore \frac{e}{R} = \frac{\left(1 + \frac{J^2}{4 R^2} \right) \frac{\alpha}{2} - \left(1 - \frac{J^2}{12 R^2} \right) \frac{\sin \alpha \cos \alpha}{2} + r m \frac{\pi}{2}}{\left(1 + \frac{J^2}{12 R^2} \right) \sin \alpha - \alpha \cos \alpha - r m \pi \cos \alpha}$$

$$\text{Also } \frac{W}{R J} = \frac{2 c_w}{1 + \frac{1}{2R} - \cos \alpha} \left\{ \left(1 + \frac{J^2}{12 R^2} \right) \sin \alpha - \alpha \cos \alpha - r m \pi \cos \alpha \right\}.$$

For all practical purposes higher powers of $\frac{J}{R}$ may be neglected

$$\text{Then } \frac{e}{R} = \frac{\alpha - \sin \alpha \cos \alpha + r m \pi}{2(\sin \alpha - \alpha \cos \alpha - r m \pi \cos \alpha)} \quad \text{----- (1)}$$

$$\text{and } c_w = \frac{W}{R J} \times \frac{1 + \frac{1}{2R} - \cos \alpha}{2(\sin \alpha - \alpha \cos \alpha - r m \pi \cos \alpha)} = \frac{W}{R J} \times K_w \quad \text{--- (2)}$$

Also, if t_w = max. tensile steel stress,

$$\frac{t_w}{m c_w} = \frac{R + R \cos \alpha}{R + \frac{1}{2} - R \cos \alpha} \text{ or } \frac{t_w}{c_w} = \frac{m(1 + \cos \alpha)}{1 + \frac{1}{2R} - \cos \alpha} \quad \text{--- (3)}$$




Fig. 2.

The three essential formulæ in the foregoing are:

$$\text{Eccentricity ratio: } \frac{e}{R} = \frac{\alpha - \sin \alpha \cos \alpha + \pi r m}{2(\sin \alpha - \alpha \cos \alpha - \pi r m \cos \alpha)} \quad (1)$$

Compressive stress in concrete:



$$c_w = \frac{W}{R J} \times \frac{1 + \frac{J}{2R} - \cos \alpha}{2(\sin \alpha - \alpha \cos \alpha - \pi r m \cos \alpha)} = \frac{W}{R J} K_w \quad (2)$$

Tensile stress in reinforcement:

$$t_w = \frac{m(1 + \cos \alpha)c_w}{1 + \frac{J}{2R} - \cos \alpha} \quad (3)$$

The charts in Figs. 2 to 5 are based on these formulæ with $m = 15$, which is the value of the modular ratio commonly used. Separate charts are given for ratios of $\frac{J}{R}$ equal to 0.06, 0.10, 0.12, and 0.18.

APPLICATION OF CHARTS.—The procedure for using the charts, assuming that J , R , e , and p (or r) are known or can be determined, is to select the chart from Figs. 2 to 5 giving the nearest value of $\frac{J}{R}$. Calculate $\frac{e}{R}$ and follow along the






Fig. 5.

abscissæ to the intersection with the appropriate curve of p (or r); read on the chart the corresponding value of K_w and substitute this value in $K_w \frac{W}{RJ}$ to give c_w . Also read on the chart the corresponding value of $\frac{t_w}{c_w}$ to give t_w .

The values of $\frac{J}{R}$ for which the charts are drawn are practical ratios, and after a little inspection and use it is relatively simple to interpolate between them to suit the diameter and thickness of shaft assumed in the first design. If the calculated stresses are too high or too low, a simple adjustment is made to J , or J_s , which are the only variables, and the process is repeated.

Example.

Calculate the stresses at a horizontal plane in the shaft where the weight W is 978,000 lb. and the bending moment M due to the wind is 5,088,000 ft.-lb. The external diameter of the shaft is 17.75 ft. and the thickness is 7 in.

Therefore $e = \frac{M}{W} = \frac{5,088,000 \times 12}{978,000} = 62.5$ in. If the thickness J of the shaft is 7 in., $R = \left(\frac{17.75 - 0.58}{2} \right) = 8$ ft. 7 in. Therefore $\frac{e}{R} = \frac{62.5}{103} = 0.606$, and $\frac{J}{R} = \frac{7}{103} = 0.068$. If the vertical reinforcement at this level is 132 $\frac{1}{8}$ -in.

bars, the cross-sectional area of the reinforcement is 79.33 sq. in., and

$$r = \frac{J_s}{J} = \frac{79.33}{7 \times 2\pi \times 103} = 0.017.$$

Using the curves in *Fig. 2*, that is for $\frac{J}{R} = 0.06$, stresses slightly lower than the actual stresses will be obtained. For $\frac{e}{R} = 0.606$ and $r = 0.0175$, read $K_w = 0.29$ and $\frac{t_w}{c_w} = 2.1$. Therefore

$$c_w = \frac{K_w W}{R J} = \frac{0.29 \times 978,000}{103 \times 7} = 395 \text{ lb. per square inch,}$$

and $t_w = 2.1 \times 395 = 830 \text{ lb. per square inch.}$

Using the curves in *Fig. 3* for which $\frac{J}{R} = 0.10$, stresses slightly greater than the actual stresses will be obtained. $K_w = 0.30$ and $\frac{t_w}{c_w} = 2.2$. Therefore $c_w = 410 \text{ lb. per square inch}$ and $t_w = 900 \text{ lb. per square inch.}$

Interpolating between the stresses for 0.06 and 0.10 for 0.068, $c_w = 400 \text{ lb. per square inch}$ and $t_w = 850 \text{ lb. per square inch.}$

Repeated Loading of Beams.

ACCORDING to the annual report of the Building Research Board ("Building Research 1958," H.M. Stationery Office. Price 5s. 6d.) tests made at the Building Research Station show that where failure of prestressed concrete beams is due to fatigue of the steel, the ratio of the maximum value of the repeated load just insufficient to cause failure after one million repetitions to the static load causing failure was between 0.65 and 0.85. The lower ratio was obtained with deformed wires and the higher ratio with plain wires that had been subjected in manufacture to a final heat treatment at relatively low temperature. For failure due to fatigue of concrete in compression, the ratio was between 0.77 and 0.82 whether the concrete was made with rapid-hardening Portland cement or with high-alumina cement. Where failure due to fatigue occurred large deflections and extensive cracking developed before collapse became imminent.

Failure under repeated loading of reinforced concrete beams with mild steel reinforcement occurred as a result of yield-

ing of the steel. The ratio of the repeated load just insufficient to cause failure to that causing failure under static conditions was about 0.9. For beams reinforced with cold-worked deformed bars, failure under repeated loading was due to fatigue of the steel; the ratio for these beams was about 0.7.

In the case of prestressed and reinforced beams repeated loading within the range of the working load had little effect on subsequent behaviour, and repeated loading with a maximum load closely approaching that causing failure due to fatigue could be sustained without reducing the strength under static loading.

Tests on prestressed beams under static loading support the suggestion that the permissible bending tensile stress used in design should be related to the initial precompression in the concrete, and indicate that simple relationships can be used for calculating the strength of beams with pre-tensioned wires or post-tensioned and grouted cables or bars provided that the design and construction conform to current practice.

Elevated Road, Chiswick, London.

THE elevated road (Fig. 1) which passes over other roads, a roundabout, and railways between the Great West Road and the extension of Cromwell Road has two carriageways each 24 ft. wide separated by a central reservation, and verges about 5 ft. wide along each outer side. Access to the roundabout is by means of four slip-roads.

The part over the roundabout comprises four freely-supported spans 125 ft. long and 59 ft. wide, and a bridge in the approach with a skew span is 70 ft. long and 124 ft. wide. The approaches and the road between the bridges are on embankments retained between plain concrete walls faced with brick. The filling is of gravel containing between 5 per cent. and 15 per cent. by weight of material passed through a No. 200 sieve, and compacted in 9-in. layers by means of 8-tons smooth rollers. After compaction the material had about $7\frac{1}{2}$ per cent. of voids; near the retaining walls and abutments vibrating-plate compactors were used to reduce the voids to about 5 per cent.

The Main Bridge.

The abutments and the two easterly piers of the longer bridge are on reinforced concrete rafts founded on compact gravel overlying London clay. The western pier is on a narrow piled foundation owing to the proximity of a 48-in. diameter sewer 20 ft. below ground. Ten bored piles each 3 ft. 3 in. in diameter and carrying up to 370 tons were constructed to a depth of 80 ft., 60 ft. of which are in London clay. The upper 25 ft. of each pile are reinforced. The abutments are of plain concrete with brick facings and each pier consists of five large columns which are lightly reinforced and a strongly reinforced capping beam (Fig. 2).

In each span there are fifteen concrete beams side by side (Fig. 2). Each beam was precast in three parts, the outer parts being about 38 ft. long and the central parts 48 ft. long; each part weighs about 33 tons. The strength of the concrete at 28 days was at least 7500 lb. per square inch. The members have mild steel secondary reinforcement and



Fig. 1.




Fig. 2.—Transverse Sections.

were prestressed at a factory by the Freyssinet method. They are of inverted tee-section with a narrow top flange and transverse stiffeners were cast in them. The bottom flange of each beam contains eighteen straight ducts with steel sheaths of 1½-in. diameter; the ducts terminate against steel plates cast in the ends of the beams and having a corresponding number of holes. The beams at the sides of each span are of U-section (*Fig. 2*); the aggregate is grey Cornish granite, and the exposed vertical faces are lightly bush-hammered.

The carriageway consists generally of a reinforced concrete slab 10 in. thick with an upper layer of 3½ in. of hot-rolled asphalt. Curing of the concrete was by means of a spray of bituminous emulsion. Transverse joints in the slab are at intervals of up to 120 ft., and a strip of steel fabric was laid flat on the slab at the joints before surfacing as a precaution against cracking of the asphalt. The lighting columns are of reinforced concrete and are of octagonal cross section. The road and bridges were designed to comply with the Ministry of Transport Standard Highway Loading and for the Ministry's 180-tons abnormal live load.

Owing to the congested conditions at the site the beams were made in a factory about 60 miles away and transported to the site by road. A 45-tons crane (*Fig. 3*) was used to place them on the bearings on the piers and abutments, and on temporary rollers supported on steel trestles at the transverse joints between the three parts of the beams. These joints are nominally 3 in. wide, and

continuity of the ducts across the joints was ensured by short lengths of rubber tube clipped to the ends of the projecting sheaths. The joints were filled with rapid-hardening concrete. When this concrete had attained a crushing strength of 6000 lb. per square inch (about three days after casting) the beams were prestressed by the Freyssinet method. Each duct contains twelve high-tensile wires of 0.276 in. diameter which were tensioned between anchorages bearing on steel plates embedded in the ends of the beam. The initial force applied to each cable was 113,000 lb., and the ducts are filled with colloidal grout applied under pressure.



Fig. 3.—Erecting Precast Beams.

When all the beams in one span had been erected, inflatable rubber tubes were passed into 3½-in. ducts formed in the stiffeners, and concrete was placed in the longitudinal joints and the joints between the stiffeners. A reinforced concrete slab was cast at the level of the top of the beams, and the whole deck was prestressed transversely by cables threaded through the webs and stiffeners of the beams and tensioned by the Gifford-Udall method. The anchorages are in the inner web of the U-shaped beams at the sides of the deck.

"Pinned" or rocker bearings (Figs. 4 and 5) are provided on the abutments and piers. The bearing-plates and rockers are of high-tensile corrosion-resisting cast iron and the locating pins are of stainless steel. The expansion joints in the carriage-ways, verges and reservation, above the rocker bearings, are stainless-steel sliding plates.

The Skew Bridge.

This bridge was constructed in halves longitudinally. The abutments are of plain concrete on reinforced raft founda-



Fig. 4.—"Pinned" Bearings.



Fig. 5.—Rocker Bearings.

tions and have brick facings. The deck comprises forty-three precast beams of inverted tee-section which were prestressed during manufacture by the Freyssinet method. The beams, which were made in the same factory as the beams for the main bridge, are 72 ft. long and each weighs about 24 tons. They were placed side by side on the bearings, and transverse stiffeners were cast between the beams and around metal ducts passing through the webs. The joints between the flanges were filled with concrete and a deck slab was cast at the level of the top of the beams. Each half of the deck is prestressed transversely by the Freyssinet method with cables containing twelve wires of 0.276 in. diameter passing through the transverse ducts.

At the free end each beam rests on a bearing of bonded-rubber and steel 16 in. by 11 in. by 7 in. thick and on a pad of rubber 16 in. by 11 in. by 1 in. thick reinforced with canvas at the fixed end. The greatest force at each bearing is 32 tons due to dead load and 28 tons due to live load. Each bonded-rubber bearing was tested with a force of 30 tons in compression, and also with a shearing force of 8 tons simultaneously with a force of 30 tons in compression. Bonded-rubber pads were used because of the tendency for movements due to expansion

and contraction to occur in longitudinal and transverse directions. The outer beams have grey Cornish granite aggregate and are lightly bush-hammered on the exposed faces.

The consulting architect to the Ministry of Transport was Mr. G. Stewart and the

consulting engineer was Mr. Harry Brompton. The main contractors were the Alderton Construction Co., Ltd., the piling was carried out by Braithwaite Foundations & Construction, Ltd., and the precast beams were made by the Cowley Concrete Co., Ltd.

Losses of Prestressing Force.

MR. B. K. CHATTERJEE, M.Sc., A.M.I.C.E., of Calcutta, writes as follows.

SIR,—Dr.-Ing. Jerzy Zielinski in his article on "Losses of Prestressing Force" in your number for May 1959, states that the values for the losses of prestressing force when metal ducts are used are about 50 per cent. higher than those given by Mr. Cooley's coefficients which were based on laboratory tests. I have undertaken tests on many prestressed concrete structures of long span and I am of the opinion that the coefficients suggested by Mr. Cooley can be safely recommended for application under site conditions. Reference should be made to an article entitled "Friction Losses in Prestressing under Site Conditions" in "Civil Engineering and Public Works Review", July, 1956, in which Mr. J. Bobrowsky and myself describe the checking of Mr. Cooley's coefficients under site conditions during the prestressing of the edge-beams of the shell roof of the assembly hall at Kidbrooke Comprehensive High School, London. The cables are in groups and are about 75 ft. and 86 ft. in length. It was realised that in order to avoid errors due to the cables being of parabolic shape the different radii of curvature at various points had to be correctly determined, as described in the article where the results of some tests are given. The Freyssinet system of prestressing was used with twelve wires of 0.2 in. diameter in metal tubes. Moderate vibration during the consolidation of concrete was assumed. Forty cables were tested and the maximum deviation from the theoretical values (using Mr. Cooley's coefficients and our method of dealing with parabolic curves) was only 2.22 per cent. A typical result was a deviation of 2.02 per cent.

DR.-ING. JERZY ZIELINSKI replies as follows.

Mr. Chatterjee's letter gives me the opportunity to point out a specific factor regarding the losses of prestressing force due to friction which I think may be useful in promoting better understanding of the problem.

One of the most important factors influencing the losses of prestressing force in straight cables is the stiffness of the metal sheaths. Since different types of sheath are used in various countries, it was thought that it would be useful to compare the losses obtained with the metal sheaths described by Mr. Cooley with other sheaths. In particular, the metal sheath 0.15 mm. to 0.25 mm. thick produces, as reported, a coefficient of loss (K) per metre length of 1.52 per cent. Nearly the same value of K is obtained in preformed ducts when metal sheaths 0.6 to 0.8 mm. thick are used. Both these values are about 50 per cent. higher than those given by Mr. Cooley (Table I, point 2, column 5, in "Estimation of Friction in Prestressed Concrete", Cement & Concrete Association, 1954), whereas some values of K , for example, for sheaths 0.8 mm. thick, which were probably similar to those used by Mr. Cooley, agree well with those given by him, namely 0.90 per cent. in my tests and 1 per cent. in Mr. Cooley's tests.

Therefore, the results I was able to publish had to justify the opinion that Mr. Cooley's coefficients should be checked when they are used for metal sheaths other than those specified by him. It was never my intention to correct Mr. Cooley's coefficient as he used it, as seems to be implied in the comment by Mr. Chatterjee.

Book Reviews.

"Vibration Engineering." By W. Ker Wilson (London: Charles Griffin & Co., Ltd. 1959. Price 90s.)

The theory of mechanical oscillation and the reduction of vibration is dealt with in great detail, but in general the emphasis is on the effects of vibration on machines rather than on the supporting structures. In the first part, which occupies about a third of the book, the balancing of machines in order to reduce vibration is considered, but in the second part there is more matter that may be of interest to structural engineers. The isolation of vibrating machines is dealt with first by giving methods of determining the frequency of vibration, followed by descriptions of, and calculations in connection with, anti-vibratory mountings such as suspension links, springs, and rubber pads. In most of the problems discussed it is assumed that the machine and its flexible mountings are supported on a rigid and inelastic foundation, which is an acceptable assumption in general as regards the machine. The author explains that the natural frequency of a block of concrete embedded in the ground may generally be between 1000 and 2000 cycles per minute, but in marshy ground it may be as low as 500 cycles and on rock as high as 4000 cycles. The results can be serious if the frequency of vibration of the machine coincides with that of the ground. Some guide to the avoidance of this condition is given in connection with foundations and machines on upper floors of buildings. The effect of vibrations of the ground being transmitted through the foundations to the machine is also considered.

The principal numerical example is of a small oil-engine driving a generator and founded on a concrete base. The treatment is mainly from the mechanical aspect, but the effect on the ground and means of damping vibrations to avoid causing damage to adjacent structures are considered. A structural engineer might expect to find in this book an example of the design of large elevated substructure for a turbo-generator but, although the basic principles may be contained in the mathematics, this specific problem is not considered. The mathematics is in general so complex that the first chapter is devoted to an explanation of the use of digital computers.

"Die zweiseitig gelagerte Platte." By Hugo Olsen and Fritz Reinitzhuber. (Berlin: Wilhelm Ernst & Sohn. 1959. Price 24 D.M.)

THIS book deals with the design of slabs supported along two edges. Data are provided for the calculation of the bending moments and deflections of freely-supported slabs of any ratio of span to width, based on the differential equation for the loaded slab. It is shown that for a slab having a ratio of span to width of 1:4 and carrying a uniformly-distributed load p over the entire area, and assuming Poisson's ratio to be 1:6, the bending moment in the unsupported direction is $0.02083pl^2$ or $16\frac{2}{3}$ per cent. of the bending moment $0.125pl^2$ in the direction of the span l . If distribution reinforcement is provided in accordance with the recommendations of the British code of practice there is sufficient steel to resist the longitudinal moments calculated by the authors' method.

"Bauforschung 1945-1958." Vol. I. Compiled by Deutsches Bauzentrum e.V. (Stammheim-Calw: Lothar Rossipaul. 1959. Price 16 D.M.)

THIS is a list of references to German literature on building research during the period 1945 to 1948. Publications concerned with concrete and cement are listed under Cement, Mortar and concrete, Aggregates, Admixtures, Porous concrete, Lightweight concrete, Testing, Precast concrete, Construction, and Prestressed concrete. Only the names of the authors and publishers and the title of the publication are given.

"Zur Theorie und Berechnung von Schalentragwerken in Form gleichseitiger hyperbolischer Paraboloiden." By Werner Bongard. (Berlin: Wilhelm Ernst & Sohn. Price 7.60 D.M.)

THE theory of thin saddle-shaped structures of hyperbolic paraboloidal form and the calculation of stresses in them are described in this thesis. An approximate theory of bending is developed, and equations which require the use of an electronic computer for their solution are derived for use in calculating deformations, bending moments, and shearing forces.




FIG. 1.

Prestressed Bridge over the River Medway.

PRECAST SUSPENDED GIRDERS WEIGHING 165 TONS.

A BRIDGE (Fig. 1) 325 ft. long and 87 ft. wide to carry the Maidstone by-pass road over the River Medway is being constructed of prestressed and reinforced concrete. The deck comprises a balanced cantilever, two suspended spans, and an end span with a short cantilever.

The main span is 145 ft. long. There will be two carriageways each 24 ft. wide, a central reservation 15 ft. wide, and two pavements each 8 ft. wide. The lack of symmetry of the bridge is caused by the difference of 40 ft. between the levels of the banks of the river and by the requirement that a tow-path at least 15 ft. wide be provided on one bank. It was also required that provision be made for a possible future widening of the river and that no temporary supports be placed in the river during construction. The height of the bridge is controlled by the need to provide clearance over an adjacent rail-

way which is considerably higher than the river.

The deck (Fig. 2) comprises slabs 10 in. thick supported on four hollow girders of prestressed concrete with internal transverse walls at intervals of about 10 ft. and which are stiffened by transverse reinforced concrete beams cast in place at intervals of about 20 ft. along the length of the bridge. The walls of the girder vary in thickness between 1 ft. 2 in. and 1 ft. 6 in., and the top and bottom flanges generally vary in thickness between 10 in. and 1 ft. but are thicker near the supports.

At the east end of the bridge an open type of abutment (Fig. 3) is provided on which are supported the ends of four prestressed girders about 81 ft. long. To enable the prestressing cables to be tensioned, the girders are to be cast over their final position and later lowered on to their




Fig. 3.—Low

supports by means of jacks. On the east bank a balanced cantilever is supported on a reinforced concrete pier founded on a reinforced concrete strip footing resting on Kentish ragstone below the bed of the river. The girders for the central suspended span will be precast near the bridge and rolled into position over a temporary structure, probably a Bailey bridge. These girders will weigh 165 tons each, and are said to be the biggest to be made and erected in this way. The girders of the other span rest on bearings at the top of the western embankment and are supported on, and cantilever 20 ft. beyond, a pier at the western bank of the river.

The piers are to be constructed within steel sheet-pile cofferdams. Part of the piling on the eastern bank is to be left in place and faced with masonry and will retain the tow-path. The piling is to be tied to the footing and to the pier by horizontal 2-in. bars at intervals of about 5 ft. along the top and base of the wall, since the piles cannot be driven into the rock. The eastern pier is of reinforced concrete and is about 50 ft. high from the top of the footing to the top of the girders.

The girders forming the balanced cantilever extend about 44 ft. on each side of the pier and are to be prestressed in three stages with sixty-two cables each comprising twelve wires of 0.276 in. diameter. The girders will be 8 ft. wide, about 11 ft. 8 in. deep at the junction with the piers, and 5 ft. 10 in. deep at the ends. In the first stage of construction the girders are to be cast complete and the pier and transverse beams are to be cast to within 1 ft. 7 in. of the top. Thirty-six of the prestressing cables will then be tensioned, and will extend throughout the entire length of the cantilevered girders. The suspended girders will then be placed in position and the slabs cast on them. The slabs on the cantilevers will then be cast. In this way the bending stresses produced by the suspended spans in the slabs of the cantilevered spans will be due to the roadway and imposed loads only.

In the second stage the slabs are to be completed for a distance of 23 ft. on each side of the pier, that is as far as the first transverse stiffeners. Nine cables in each beam and nine alternate cables in each slab will be anchored at these stiffeners




Fig. 2.—Typical Cross Section.




Fig. 3.—Longitudinal Section.




Fig. 4.—Typical Reinforcement at End of Main Girders.

and will then be tensioned. The concreting will then be completed and the remaining cables tensioned at the transverse beams about 40 ft. from the pier. The cables anchored at the transverse beams will be curved downwardly for the last 10 ft. to anchors in the sides of the beams below the soffit of the slab. The cables anchored in the ends of the girders will be curved downwardly to provide resistance to shearing. Manholes will be provided for access to the anchorages inside the girders. Mild steel reinforcement will be provided to resist the stresses due to shrinking and changes of temperature, and to resist the bursting forces around the anchorages (Fig. 4).

The girders supported between the balanced cantilevers and cantilevered part of the end girders will be prestressed by forty-six cables each containing twelve wires of 0.276 in. diameter. Most of the cables are curved upwardly near the ends of the beams to resist shearing forces. These beams will be provided with mild steel rocker bearings at each end. Roller bearings will be provided at the abutments and at the top of the western pier. The embankments are to be faced with precast slabs with exposed-aggregate surfaces, and the visible sides of the main beams and piers are to be point-tooled.

It is planned to complete the bridge during a period of fifteen months and the tendered price is about £220,000. The bridge has been designed for the Ministry of Transport and Civil Aviation by Messrs. Scott & Wilson, Kirkpatrick & Partners (who are also supervising the construction) in collaboration with Messrs. Adams, Holden & Pearson acting as consulting architects. The contractors are Sir Robert McAlpine & Sons, Ltd., and the prestressing equipment is supplied by P.S.C. Equipment, Ltd.

Congress on Prestressed Concrete.

THE fourth congress of the Fédération Internationale de la Précontrainte will be held in Rome and Naples in June or July, 1962. The subjects to be dealt with include the results of research since 1958, problems at sites, accidents, fire resistance, buckling, stress corrosion, the economics of prestressed concrete structures, progress in precast manufacture and standardisation since 1958, and outstanding prestressed concrete structures constructed since 1958.

UNESCO Headquarters in Paris.

THERE are several examples of exposed concrete surfaces as architectural features in the congress hall and office building at the new headquarters of UNESCO in Paris. To obtain the finish required the use of plywood and metal shuttering was prohibited. Many of the surfaces show intentionally the marks of the joints between the narrow boards used for the shuttering.

The hall (*Fig. 1*) is trapezoidal in plan and is 154 ft. long and tapers from 197 ft. to 111 ft. 6 in. in width. The roof and the end walls are constructed of twelve double-bay rectangular frames the main

members of which are basically of vee-section, and are carried on a central support comprising a transverse beam supported by a row of columns. The concrete in the spaces between the members was cast after most of the shrinking of the main members had taken place. A thin curved slab interpenetrates the roof members over the auditorium. The surfaces of the end wall (*Fig. 2*) and roof of the auditorium have a pattern formed by the joints between shutter-boards $2\frac{1}{2}$ in. wide. The wall was cast in 4-ft. 6-in. lifts, and the top of each lift is emphasised by a horizontal rebate. The




Fig. 1.—Section through Main Hall.




Fig. 2.—Wall behind the Rostrum.




Fig. 3.—Canopy at Entrance.

columns in the foyer, which are of circular cross section at the base and rectangular at the top, have been lightly rubbed and the marks left by the narrow shutter boards are faintly visible. The walls of the entrance to the auditorium are bush-hammered.

The office building comprises seven upper stories supported on columns in the ground-floor story, the shape of the columns varying from a narrow pentagon at the top to an ellipse at the bottom as shown in Fig. 4. The narrow shutter-boards for the columns were so placed that the joints formed a pattern of horizontal lines on some faces and vertical lines on others. The canopy over one of the entrances (Fig. 3) comprises two thin doubly-curved slabs, which are cantilevered, one on each side, from a central arch. The surfaces of the curved slabs exhibit the marks of the joints of the narrow shutter-boards which are parallel to the longitudinal axis of entrance.




Fig. 4.—Columns in Ground Story.

The buildings were designed by M. Breuer, B. Zehruss, and P. L. Nervi. The contractors were Fourré and Rhodes-Dumez. The foregoing and the accompanying illustrations are from the "Concrete Quarterly" for January-March, 1959.

Measuring Temperatures in Concrete.

AN investigation of the use of thermistors for measuring temperatures in concrete has been made by Mr. Knud E. C. Nielsen at the Swedish Cement and Concrete Research Institute, and the results are given in a bulletin entitled "Temperature Measurements with Thermistors in Concrete" (price Kr. 8). Chapters deal with the properties of thermistors and methods of measurement, and examples of their use are given. It was found that the temperatures recorded were accurate to about 0.1 deg. C., and that the thermistors were cheap, simple to calibrate and to use, and were not damaged when they were used on construction sites. The tests included measurements of the temperature in the interior of (a) concrete subjected to alternate freezing and thawing, (b) concrete subjected to loading (in order to ascertain the internal stresses), (c) concrete placed under water (in order to ascertain the time of setting so as to determine a suitable rate of placing further concrete).

Bridges on the London-Birmingham Motorway.

THE construction of much of the London-Birmingham motorway, which was described in this journal for October last, is now complete. Fifty-five miles of dual carriageway, including more than 120 bridges from near Luton to near Rugby, are now open to traffic and were constructed in nineteen months. Thirteen of the bridges to the south-west of Northampton were constructed by sub-contractors and comprised two wall-and-slab viaducts, an arch bridge over a canal, a bridge over the railway, and nine two-span bridges over the motorway, and these are briefly described in the following.

At the crossing of the River Nene there

at the bottom to 1 ft. at a height of 16 ft. Openings with semi-circular heads (*Fig. 1*) are formed in the piers to reduce their weight. The viaduct over the relief channel is similar in detail but has nine equal spans. Although the river and the relief channel are narrow, these viaducts have been provided to span the flood plains on either side, and are 376 ft. and 357 ft. long respectively. Severe flooding was encountered during construction.

The bridge over the Grand Union canal at Milton Ham is of plain concrete and has a span of 40 ft. It is supported on reinforced concrete piles up to 60 ft. long. The soffit of the arch is 32 ft. above the




Fig. 1.—Construction of Piers of Nene Viaduct.

are two viaducts with reinforced concrete decks carried on ten piers, each 120 ft. long. The span at the river crossing is 56 ft. between the piers; the remaining ten spans are each of 28 ft. The deck over the side spans is 1 ft. 9 in. thick, with the exception of the slabs on either side of the long span which are 3 ft. thick and are extended to cantilever 14 ft. over the river from each side. A slab 28 ft. long over the river is carried on the two cantilevered slabs.

Plain concrete foundations extend to 15 ft. below the level of the ground and support the reinforced concrete piers, which vary in thickness from 2 ft. 10 in.

to 4 ft. 6 in. at the top. The motorway is on an embankment about 50 ft. above the level of the natural ground. The wing walls are 204 ft. long. The fascias of the arch are parabolic on plan. Construction of the arch was carried out by means of a travelling shutter.

Two of the two-span over-bridges of standard design to carry existing roads over the motorway form part of an elevated roundabout, where slip-roads lead on to and out of the motorway. To allow for the different angles at which the motorway is crossed the lengths of the abutments and lengths of the spans are different, although all the bridges on the



Fig. 2.—Bridge over a Railway.

major and minor roads have a similar appearance. The widths of the decks are from 32 ft. to 42 ft. 6 in., the square span between the abutments is 123 ft. in all cases, and the lengths of the abutments are up to 95 ft. The superstructures of the bridges are entirely of reinforced concrete. The foundations are of plain concrete, but in some cases the structures are founded on precast reinforced concrete piles. The cylindrical central piers are 4 ft. 6 in. in diameter and support beams which carry the deck, which is generally 2 ft. thick.

The railway bridge was constructed in such a way that interference with the use of the railway was as little as possible. Plain-concrete abutments and reinforced concrete beams carried on cylindrical columns support precast reinforced concrete inclined beams as shown in Fig. 2. The beams form the soffit of a sloping reinforced concrete slab on each side of the bridge and which is cantilevered over the tracks. Precast reinforced concrete deck beams were then placed to span between the two cantilevers and form the soffit of a reinforced concrete slab cast in place by means of which the structure is made monolithic. The tarmacadam surface of the road was laid directly on this slab. (This type of bridge is described in this journal for March 1958 and October 1959.)

The thirteen bridges included in this sub-contract were commenced in May 1958, and completed in January 1959, before the road-making machines reached each site. Each over-bridge was constructed in about twenty weeks, and the

other structures in twenty to thirty weeks each. Shuttering faced with plywood was used throughout.

The consulting engineers to the Ministry of Transport and Civil Aviation are Sir Owen Williams & Partners. The main contractors were Messrs. John Laing & Son, Ltd., and the sub-contractors for the thirteen bridges described in the foregoing were Messrs. Holloway Brothers (London), Ltd.

Rapid Road Construction.

THE Watford branch of the St. Albans by-pass road, which is the continuation southwards of the Rugby-Luton part of the London to Birmingham motorway, has been completed several weeks before the scheduled date. The branch comprises dual concrete carriageways 26 ft. wide, the construction of which was described in this journal for October, 1959. It is claimed that a record for concrete road construction in Great Britain was established by laying 1320 ft. of 26-ft. carriageway in eleven hours. The total cost of the Watford branch is about £1,250,000, and the value of the equipment installed to hasten construction was nearly £1,000,000. The contractors for the Watford branch are a consortium comprising Messrs. Holland & Hannen and Cubitts (Great Britain), Ltd., Messrs. Fitzpatrick & Sons (Contractors), Ltd., and Messrs. Lehan, Mackenzie & Shand, Ltd.

A New Type of Cast-in-Place Pile.

FIVE hundred piles of a new type (known as Delta) are used to support oil-storage tanks and a boiler-house at the depot of Shell Mex & B.P., Ltd., at Wandsworth, London. The piles are 30 ft. long and are founded on ballast underlying poor clay and made-up ground.

The piles are of a Swiss type introduced recently into this country, and may be reinforced or not. The stages in the construction of an unreinforced pile are indicated in *Fig. 1* and are: (1) Pitch the driving tube on a reinforced concrete shoe with a small quantity of concrete between a steel mandrel and the shoe. (2) Drive the tube to the required level or set by means of a diesel-driven hammer. (3) Insert sufficient concrete in the tube to form a bulb. (4) Using the hammer and mandrel, ram the concrete while withdrawing the tube slightly, thus forming a bulb of concrete. (5) Fill, or partly fill, the tube with concrete, and, with the hammer and mandrel resting on the concrete, withdraw the tube. (6) Insert reinforcement to connect with the superstructure if required. Operation No. 5 may be carried out in one step for the entire pile or in several steps for longer piles. If the pile is to be reinforced, the method is basically as described, but four bars are attached to the mandrel between operations Nos. 3 and 4. The bars are

attached to the mandrel with wire which breaks when starting to ram to form the bulb.

To take advantage of good intermediate bearing strata, extra bulbs can be made on the pile by interrupting operation No. 5 at the required depth and repeating operations Nos. 3 and 4. If the bearing stratum is poor, larger bulbs can be produced by introducing extra concrete in operation No. 3 and withdrawing the tube correspondingly farther in operation No. 4.




Fig. 1.—Stages of Forming a Pile.



Fig. 2.

December, 1959.

For longer piles the tube and mandrel can be lengthened.

Fig. 2 shows a pile being formed. The tube, which is partly filled with concrete, is being withdrawn after the formation of the bulb and while the hammer and mandrel are resting on the concrete. The diameter of the shoe is 1 ft. 7 in., and the nominal diameter of the shaft is

1 ft. 4½ in., which is the external diameter of the tube; the size of the shaft is likely to be larger due to the fact that the concrete is forced into the ground surrounding the tube. The tube is 39 ft. or 42 ft. long, but can be extended to 65 ft. or 75 ft. The diameter of the bulb is not less than 3 ft.

The licensees for the system are H.D. Foundations, Ltd.

Hydrographical Folly from B.S.I.

"Tests for Water for Making Concrete."

British Standard No. 3148:1959. (London: British Standards Institution. Price 35.)

A SIMPLE method of ascertaining the suitability of water for making concrete would often be useful, but it is not given in this document. The committee of representatives of two research organisations, six professional institutions, and three trade associations which studied the problem say that it has failed to find a satisfactory method, and instead is content to recommend that specimens be made of cement paste to determine the initial setting-time and of concrete to determine the crushing strength, and that the results be compared with similar specimens made with distilled water. This is no doubt what their grandfathers did. In an appendix it is stated that the committee "considers" that the water will be suitable if the initial setting-time does not differ by more than thirty minutes from that of the specimen made with distilled water, and if the crushing strength at 28 days is not less than 80 per cent. of that of the specimens made with distilled water—but it is only "believed" that the strength of such concrete will not subsequently decrease by reason of the quality of the water. So, after making the specimens and waiting for twenty-eight days to know the results of the crushing tests, the effect of the doubtful water is still not known.

The whole of the useful information in this document is given in the foregoing, with the exception of references to five other British Standards that must be bought and consulted for guidance in making and testing the specimens. If the useless, and sometimes laughable, matter

were omitted the standard could have been printed on one side of a sheet of paper and sold for a few pence. Seldom can even the British Standards Institution have offered so little information at so high a price. The fecundity of the Institution is indicated by the fact that this Standard is numbered 3148. This one at least is unnecessary, for it is quite wrong to call it a standard or a specification when the comments in the appendix indicate that the committee has no knowledge of the validity of the recommendations it makes.

A French standard issued in the year 1941 gives recommendations for the acceptable limits of matter in suspension (2 grammes per litre) and of dissolved salts (15 grammes per litre), and a still earlier U.S.A. recommendation gave permissible values for the acidity and alkalinity of water for making concrete. This is the kind of guidance that is wanted, and which this so-called standard specification fails to give.

Measuring the Air Content of Concrete Mixtures.

AN apparatus for measuring the quantity of air in concrete mixtures, and the specific gravity and the amount of free moisture in aggregate, is now available. The container has a capacity of ¼ cu. ft. of the material to be tested, and so provides a means of measuring its density. A nomograph supplied with the apparatus enables the specific gravity and the percentage of free moisture of the aggregate to be determined. The principle used is Boyle's law. The apparatus weighs about 12 lb. and is obtainable from Soiltest, Inc., Chicago, U.S.A.

Accelerated Tests for Cement.

Mr. T. N. W. AKROYD writes as follows.

The Editorial Note in your October, 1959, number on an accelerated test for cement was provocative and thought-stimulating, as are many of your editorials.


The test you describe appears to be limited to cement, whereas there exists an accelerated-cured compression test for concrete by which the strength of a wider range of concrete can be predicted. In addition, this test has the advantage that it relates to British Portland cements.

In November, 1955, Professor J. W. H. King described the oven-method of accelerated curing, and in February, 1956, Mr. R. G. Smith-Gander and the writer described their method whereby concrete cubes are boiled in water. I advocate the accelerated test by boiling concrete cubes in water because it is simple and easy to perform.

The boiling test is made as follows.

Half an hour after mixing and casting the concrete cubes in cast-iron moulds a steel plate is placed over the top of the cubes, which are then placed in a thermostatically-controlled curing tank where they remain in their moulds for twenty-four hours. At the end of this time they are removed from the tank and, in their moulds, are plunged into boiling water and boiled for 3½ hours. They are then removed from the boiling water, the moulds removed, and the density of each cube measured, and one hour after they are removed from the water the cubes are tested in compression.

When the original accelerated-curing test was devised it was necessary to prepare a separate graph for each type of cement and aggregate. A series of accelerated-curing tests had to be made to relate the accelerated-cured strength to the strength at seven or twenty-eight days. With the procedure described, however, in the case of most Portland cements the accelerated strength bears the same relationship to the seven-days' strength as does the seven-days' strength to the strength at twenty-eight days, so that knowledge of the strengths at seven and twenty-eight days only is required. This may be obtained from actual results or from the graph, which has been prepared from a graph relating the water-cement ratio to the strengths at seven



and twenty-eight days in the report by Mr. H. C. Erntroy, "Variation of Works Tests Cubes", published by the Cement & Concrete Association.

Effect of Calcium Chloride on Steel Reinforcement.

In concrete made with ordinary Portland cement and containing 2 per cent. of flaked calcium chloride (about 1.4 per cent. anhydrous calcium chloride), cured at normal temperatures with subsequent storage up to one year outdoors, only some discoloration and very slight local corrosion was found. The amount of corrosion increases as the calcium-chloride content is raised, or when specimens are cured and stored at higher temperatures. —"Building Research 1958." H.M. Stationery Office. Price 5s. 6d.

A Code for Prestressed Concrete.

B.S. Code of Practice No. 115 (1959), "The Structural Use of Prestressed Concrete in Buildings" (price 8s. 6d.), was published last month by the British Standards Institution. The code includes clauses on definitions and symbols, materials, stresses, losses, design of beams and compression members, statically-indeterminate structures, tensioning systems, workmanship, and testing.

Alteration of Tenders.

THE Joint Consultative Committee of Architects, Quantity Surveyors, and Builders has issued a Code of Practice for Selective Tendering, with sections on The list of tenderers, Invitations to tender, Tender documents, Form of tender, Time for tendering, Opening tenders and notifying results, and Examination and adjustment of the priced bills.

In an introduction it is stated that in no circumstances should a tendered price be altered, and the following clause is included for guidance in cases where errors in pricing need correction before a tender is accepted.

"The examination of the priced bills of quantities should be made by the quantity surveyor who should treat the document as strictly confidential: on no account should any details of the tenderer's pricing be disclosed to any person except the architect unless with the expressed permission of the tenderer.

"The first object of the examination is the detection of errors of an extent that might cause the tenderer, when he is aware of them, to withdraw his tender. If the quantity surveyor finds such errors he should report them to the architect, who should indicate to the tenderer the value of the errors and give him the opportunity of confirming or withdrawing his offer. If the tenderer withdraws, the priced bills of the second lowest should be examined. When a tender is found to be free of serious error, or the tenderer is prepared to stand by his tender in spite of an error, then the architect should inform the tenderer of its acceptance: before doing so, the architect would be well advised to obtain authority from the building owner.

"The method of adjusting any such errors should be to add an endorsement to the priced bills indicating that all rates or prices (excluding preliminary items, prime cost and provisional sums) inserted therein by the tenderer are to be considered as reduced or increased in the same proportion as the corrected total of priced items exceeds or falls short of the original total of such items. This endorsement should be signed by both parties to the contract."

Copies of the Code are obtainable (price 2s.) from the Committee at 82 New Cavendish Street, London, W.1.

Chimneys 500 ft. High at a Generating Station.

THE tallest reinforced concrete chimneys constructed up to the present in Great Britain are two chimneys 500 ft. high (Fig. 1) at the generating station of the Central Electricity Generating Board at Northfleet, Kent. The internal diameters are 38 ft. at the bottom and 23 ft. at the




Fig. 1.

top. The thickness of the wall of the shaft is 1 ft. 7 in. at the bottom and 6 in. for a distance of 175 ft. from the top. The chimneys are on raft foundations. Cement of khaki colour is used in the concrete. The external faces are coated with acid-resistant paint for a short distance from the top. The consulting engineers are Messrs. L. G. Mouchel & Partners and the contractors Messrs. Tileman & Co., Ltd.

A Prestressed Precast Bunker.

A COAL bunker (Fig. 1) 90 ft. long, 16 ft. wide, and 15 ft. deep, having a capacity of 500 tons and built recently at Girimint Colliery in West Bengal, is constructed of precast prestressed concrete units assembled and tied together with post-tensioned cables. The bunker spans a rail track and has a clear height of 16 ft. 7 in. above the rails. The two rows of eleven columns are 16 ft. apart transversely. The columns are at 9 ft. centres longitudinally, and were precast and set in pockets 9 in. deep in the foundation. Each column is 18 in. by 9 in. in cross section and 39 ft. 6 in. long, and is in three parts placed end to end through which pass four cables each comprising three wires.

Each transverse beam is in four parts each 4 ft. deep and 9 in. wide through which pass four cables each comprising twelve wires. The beams are carried on corbels on the columns and a cable of eight wires passes through each beam and its supporting columns and ties the beam and two columns together to form a frame. The longitudinal beams are 1 ft. 6 in. wide and comprise successive lengths of 9 ft. each carried on corbels on the columns. A cable of eight wires, which passes through the beams and columns, extends the entire length of the bunker. The wires in all the cables are 0.276 in. diameter and the tensile stress after an assumed reduction of 15 per cent. is 65 tons per square inch. Colloidal cement grout was injected into the ducts for all the cables.

Precast floor slabs 2 ft. 6 in. wide and 7 in. thick are supported on the transverse beams. Openings in the slabs are provided for the outlets, the steel gates of which are 2 ft. square.

The walls are of precast prestressed slabs 1 ft. 9½ in. wide set in grooves in the faces of the columns. The slabs in the longitudinal walls are 3 in. thick in the lower part and 2½ in. thick in the upper part. The slabs in the end walls are 5½ in. and 4 in. thick. The floor and wall slabs are prestressed by pre-tensioned wires 0.159 in. in diameter which were obtained by unravelling steel-wire ropes designed from collieries. The stress in these wires is 63 tons per square inch after




Fig. 1.

allowing for a reduction of 20 per cent. Half-round grooves along the top and bottom edges of the wall slabs accommodate a 0.276-in. post-tensioned wire in alternate horizontal joints and passing through the columns. Each pair of columns is tied by a transverse ¾-in. mild steel bar at each of the quarter-points of the depth of the bunker. A transverse beam, prestressed by a cable containing eight wires, extends across the bunker between the tops of each pair of columns and carries a conveyor.

The crushing strength of the concrete was 5000 lb. per square inch at twenty-eight days. Under ordinary working conditions the calculated maximum compressive stress in the concrete is 1650 lb. per square inch and there is no tensile stress, but should the coal be stored to a height of 5 ft. above the normal level the tensile stress in the concrete of the wall slabs would be 250 lb. per square inch.

The consulting engineer is Mr. S. P. Banerjee of Calcutta. The contractors were the Indian Patent Stone Co., Ltd., who also made the precast members. Gifford-Udall anchors were used for the cables.

Glass-fibre Shuttering.

MOULDS made of glass-fibre were used for the shuttering of columns with splayed heads (Fig. 1) cast in place at premises for the Gravesend Co-operative Wholesale Society, Ltd. A mould for an interior column comprises two identical parts (one of which is shown in Fig. 2) which are fixed together by $\frac{3}{8}$ -in. bolts at 9 in. centres through the abutting flanges of each half. For a wall column one half only is used, with timber to form the flat surface.

The halves of the mould are formed on a plaster model of half a column. The model is laid on a floor with the curved surface uppermost and is treated with three coats of shellac. The shellac is polished with wax and painted with polyvinyl-alcohol in order to prevent the mould adhering to the model. A layer of polyester-resin is then applied with a brush, and a sheet of glass-fibre weighing $1\frac{1}{2}$ oz. per square foot is pressed into the resin with a roller. Alternate layers of resin and glass-fibre are applied until the mould is of a thickness such that it weighs about 6 oz. per square foot. Steel angles are embedded in the edges of the mould to strengthen the flanges, and a piece of steel strip is partly embedded in it to strengthen it longitudinally. Further pieces of steel strip are partly embedded in the other direction,



Fig. 2.—Half a Mould.

and also in the part to form the flared top. The inner face is polished.

The moulds are light in weight, non-corrosive, and translucent, and do not require to be cleaned after use. The surface of concrete cast in the moulds (Fig. 3) is smooth and is free from blemish if the concrete is consolidated by vibrators. The moulds are said to offer great resistance to abrasion, do not become distorted, can be used many times, and can be quickly assembled and dismantled.

The architect for the building is Mr. W. J. Reed, F.R.I.B.A., and the contractors were the Co-operative Wholesale Society, Ltd. The moulds were made by D.A. Models, Ltd.




Fig. 1.—Mould ready for Concreting.




Fig. 3.—Completed 12-ft. 6-in. Columns.

A Plant for Cooling Aggregate.

IN order to ensure that the temperature of the concrete does not exceed 55 deg. F. when it is placed, the aggregate used in the construction of a dam across the river Savannah in Georgia, U.S.A., is cooled in tanks of 11 ft. diameter in which during operation the pressure is reduced to less than atmospheric. The plant (*Fig. 1*) comprises three tanks 86 ft. high for the coarse aggregate and two tanks 62 ft. high for the sand. The aggregate is delivered into the top of the tanks by a conveyor. Baffles in the larger tanks distribute the aggregate throughout the vessels and reduce the abrasion against the walls. Baffles in each of the smaller tanks distribute the material in the form of cylindrical curtains of sand with air spaces between the wall of the tank and the sand.

When the tanks are charged, they are sealed and refrigeration commences. Two boilers fired with natural gas generate 34,000 lb. of steam per hour at an operating pressure of about 125 lb. per square inch. The steam is passed through a Venturi tube and the resulting reduction of pressure to about $\frac{1}{2}$ lb. per square inch is transmitted through pipes to the interior of the tanks. Because of the reduced pressure the aggregate is cooled by about 40 deg. F. in 45 minutes.

After it has cooled, the aggregate is taken by conveyor to the batching plant

and passed through screens before entering the mixer. Water for the concrete is cooled by a similar process. Cold water is circulated around the storage bins of the batching plant, although the aggregates in the bins gained only 4 deg. F. in temperature in 24 hours in warm weather when no water was circulated.

The plant is capable of cooling enough aggregate and water to produce 250 cu. yd. of concrete per hour. The tanks contain about 600 cu. yd. of coarse aggregate and 60 cu. yd. of sand and an average cooling cycle lasts about 45 minutes. These notes are abstracted from "Engineering News-Record" for April, 1959.

Lectures on Building

THE following lectures have been arranged by the Ministry of Works. Admission is free.

Work Study in the Building Industry, by R. Geary. School of Building, Fennel Road, London, S.W.4. December 15. 7.15 p.m.

Weathering and Deterioration of Concrete and Cement Renderings, by C. Hobbs. College of Further Education, Warwick New Road, Leamington Spa. December 15. 7.15 p.m.

Practical Formwork Design and Construction, by J. G. Richardson. College of Further Education, Northgate Building, Darlington. December 16. 7.15 p.m.

Wire Ropes.


THE dimensions and properties of wire ropes for use in civil engineering, mining, and other industries are given in a booklet issued gratis by the Tyne Wire Rope Manufacturing Co., Ltd., of South Shields. The data are arranged in four sections, namely ropes for mining and general engineering, ropes for lifts and elevators, ropes for excavators and other earth-moving machines, and non-standard ropes.



Fig. 1.—Cooling Aggregates.

FIFTY YEARS AGO.

From "CONCRETE AND CONSTRUCTIONAL ENGINEERING", December, 1909.



Tilt-up Construction.—What is claimed to be the first use of the tilt-up method of construction in Great Britain is described in this number in connection with some farm buildings, one of which is illustrated, in Wales. It is stated that "The system employed of forming the sides and party walls flat on the ground and afterwards raising them and jointing the corners lends itself to cheap and quick construction. The method consists in moulding the slabs on platforms, which are temporarily hinged, then rearing the platforms with the slabs on them to a vertical position, lowering the platform for use with other sections, and finally securing the segments together."

[A similar method was used for the construction of houses in the U.S.A. in 1906.]

Good jobs available with Truscon:

OFFICE	TELEPHONE	ASK FOR	REQUIRED
Birmingham	Central 2345	Mr. B. W. Cooper	Experienced reinforced- concrete designers and detailers
Glasgow	Central 0157	Mr. W. H. Sneddon	
Harlow	Harlow 24631	Mr. P. Wood	
Liverpool	Central 5281	Mr. H. Morris	
London	Waterloo 6922	Mr. E. Shepley	
Manchester	Trafford Park 3044	Mr. H. Heller	

1½ MILLION

CUBIC YARDS

OF

CONCRETE

HAVE BEEN AIR-ENTRAINED WITH

FEBCRETE A.E.A.

ON BRITISH GOVERNMENT CONTRACTS
DURING THE PAST TWO YEARS

FEBCRETE Air-Entraining Agent without adding to cost improves the flowability and workability of concrete, allows the water-cement ratio to be reduced and increases resistance to the passage of water and to repeated cycles of freezing and thawing.

It ensures that full compaction and maximum compressive strength are obtained without excessive vibration, reduces segregation of the aggregates and prevents bleeding. Write for brochure.

FEB (GREAT BRITAIN) LTD


LONDON: 102 Kensington High Street, W.8.

Telephone: WEStern 0444

MANCHESTER: Albany Works, Albany Road, Chorlton-cum-Hardy.

Telephone: CHOrlton 1063

GLASS FIBRE PAN MOULDS FOR FLOORS and shuttering for all in-situ concrete work



Glass fibre is an easily adaptable material for shuttering and moulds for all forms of concrete construction. You can see the concrete through Glass Fibre Shuttering, which enables you to check concrete placing and the concrete cover of reinforcement.

**LIGHT AS AIR
STRONG AS STEEL**

FOR HIRE
Glass Fibre Moulds
for Flooring

Consult


D. A. MODELS • LTD

108 WOODSTOCK ROAD, LONDON, W.4.

**NO STICKING
FIRM AS A ROCK**

**GLASS
FIBRE**

TELEPHONE: CHISWICK 2011



One floor of 13,500 sq. ft.
per seven days—

OMNIA Concrete Floors
contributed to remarkable
construction speed in this
major London office building

Friars House, Blackfriars, London,
occupied by Central Electricity Generating Board
Architect: Robin Seifert, F.R.I.B.A.
Quantity Surveyors: Thompson & Alexander
Consulting Structural Engineers: Reinforced Concrete Steel
Co. Ltd.
Contractors: George Wimpey & Co. Ltd.

Friars House, London, has a total of
90,000 sq. ft. of OMNIA Floors on eight
floors, using 29 ft. spans with a live load of
120 lb./sq. ft. Spine beams are contained
within the depth of the floor, giving clear
soffits without any projecting beams. Erection
was completed at the rate of one floor per
seven days—a typical OMNIA success story.
The OMNIA Floor combines precast and
in-situ methods of construction, and appeals
particularly to the Architect because it spans
economically to over 30 feet and gives a level
and unbroken soffit without camber or
bowing.



Light in weight, yet monolithic
Needs no shuttering
Easy to transport and handle
Quick and simple to erect
Spans to over 40 ft.—no camber or bowing
Economical in manufacture and installation
Adaptable in design and for services

OMNIA CONSTRUCTIONS LIMITED, 121 London Wall, London E.C.2. Monarch 2272/6

The OMNIA Concrete Floor is available
in all parts of the country from 15 OMNIA
Licensees:


THE ATLAS STONE CO. LTD., LONDON
THE BLOKCRETE CO. LTD., SOUTHAMPTON
F. BRADFORD & CO. LTD., EDMONTON
BRADLEYS (CONCRETE) LTD., DARLSTON
G. W. BRUCE LTD., ABERDEEN
T. C. CAMPBELL LTD., NOTTINGHAM
COWLEY CONCRETE CO. LTD., ABINGDON

DERWENT CAST STONE CO. LTD., MALTON
DUNBRIK (YORKS) LTD., LEEDS
EDENHALL CONCRETE PRODUCTS LTD.,

PENRITH
HYDRAULIC PRECASTS LTD., NORWICH
JAMES E. MILLAR LTD., FALKIRK
PRESTATYN PRECAST CONCRETE CO., LTD.,
PRESTATYN

ST. IVES SAND & GRAVEL CO. LTD., HUNTS
SAMUEL TYZACK & CO. LTD., SUNDERLAND

BAR-BENDING EQUIPMENT




RAS.40 MODEL

This is a single-disc machine which is specially designed for an extraordinarily high rate of bending bars up to $1\frac{1}{2}$ in. diameter.

A full hook takes three seconds' bending time. It is also equipped with accessories for bending angle loops in one operation on mild steel reinforcement up to 1 in. diameter.

HOOPS & SPIRALS

We supply, at extra cost, an appliance (illustrated here) for use with RAS.40 and ARD.50 models for the bending of hoops and spirals. Bends radii of 11 in. and upwards and to any pitch of spiral.



Our Bending Equipment also includes the ARD.50 model—a double-disc machine for bending bars up to 2 in. diameter. We also supply, at extra cost, formers and backrests for special steel such as "Square Grip," "Twistee," etc., which can be fitted to the ARD.50 and RAS.40 models. Full details are available on request. All machines are available for Sale or Hire.

CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT

Telephone: Chatham 45580.

Telegrams & Cables: Cembelgi, Chatham



EXTENSION TO
JETTY PIER No 1


FOR
NORTH THAMES GAS BOARD · BECKTON GAS WORKS

Photo by courtesy of Concrete Development Co Ltd

PETER LIND & CO LTD

ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1

TELEPHONE ABBEY 7361



35-TONS PRECAST BRIDGE SECTION

We illustrate one of the 35-ton sections produced by Anglian Building Products Ltd., of Atlas Works, Lenwade, Norwich, and 14 Stanhope Gate, London, W.1, for British Railways L.M. Region. Main Contractors: Leonard Fairclough Ltd.

WOODEN MOULD

was produced by

MAY & BUTCHER LTD

SPECIALISTS IN TIMBER SHUTTERS AND MOULDS FOR CONCRETE

More and more Contractors and Precast Concrete Makers in all parts of the country are taking advantage of the first-class service we offer in the supply of timber shutters and moulds to any design and size. This service has proved over and over again that by ordering your shutters and moulds from us you effect every possible saving in time, labour and money. However intricate the shutter or mould, you are assured of accuracy in every detail and a product with long trouble-free life. Shutters and moulds can be supplied with a plastic lining if desired. Full details of this class of work carried out by us are available on request.

HEYBRIDGE BASIN, MALDON, ESSEX.

TELEPHONE: MALDON 698/9



VINCULUM



A complete service

VINCULUM

...to the Architect



VINCULUM



and the Builder

VINCULUM

PRE-CAST CONCRETE

...for every purpose



TARMAC VINCULUM LIMITED

ETTINGSHALL, WOLVERHAMPTON Telephone BILSTON 41101 (12 Lines)

PSC

for alpr


FREYSSINET SYSTEM




... CONE
ANCHORAGE

FREYSSINET POWER EQUIPMENT ...

One of the most recent developments in the Freyssinet system of prestressing has been the introduction of power stressing. An electric or I.C. operated motor driving an hydraulic pump is trailer mounted and the hydraulic circuit has been simplified to only two controls which require the operator's attention. These are mounted on the trailer assembly and the jack is thus completely remote-controlled. The advent of power stressing has increased the rate of tensioning by three or four times that of hand pumping.



P.S.C. MONOWIRE SYSTEM




... P.S.C. ANCHORAGE

The 8/24

P.S.C. "MonoWire" Anchorage illustrated here shows a "Hydrarigid" welded seam-jointed metal sheath which screws into the anchorage. A new type of high impact plastic cable spacer is also available. These anchorages can be supplied for cables of one to twelve wires.

P.S.C. MONOWIRE POST-TENSIONING ...

This illustration shows the P.S.C. lightweight single-wire jack stressing one of twelve wires on a 12/276 "MonoWire" anchorage. The jack is available with 4" or 6" extensions, and has a spring return.



prestressing equipment



... P.S.C. GROUTING EQUIPMENT

We have made considerable investigations into the grouting of prestressed cable ducts, particularly with regard to the composition of the grout, its mixing and injection. This experience has enabled us to produce trouble-free grout injection pumps, both hand and power operated, designed specifically for cable duct grouting. The illustration shows the use of hand diaphragm-operated direct displacement grouting equipment.

P.S.C. MONOWIRE PRE-TENSIONING ...

The P.S.C. "MonoWire" pre-tensioning jack illustrated here is available with tensions from 9" to 24". The hand-operated equipment is extended hydraulically and returned pneumatically. The power-operated pump (electric or I.C.) recommended where a large number of long extensions is anticipated.




HYDRADUCT SHEATHING FOR PRESTRESSED CONCRETE

This range of sheathing includes "Hydrarigid" and "Hydraflex". It is highly efficient and easy to use, and is strong enough to take the weight of men without damage, yet flexible enough for all normal prestressing requirements. Supplied in standard lengths in diameters from 3" to 4".

... BRIDGE BEARING PADS

The Freyssli Bearing Pad, illustrated here, has proved its economy and efficiency on over 400 bridge contracts. Each pad is designed specifically for individual requirements from information obtained from a technical questionnaire, on which we ask certain design considerations. Full details are available on request.



FREYSSLI FLAT JACKS ...

Freyssli Flat Jacks are hydraulic jacks of unusual and unconventional design, which permit enormous forces to be exerted or regulated where the movement required is small. They have applications in underpinning, levelling and thrust control in engineering structures.



PSC



EQUIPMENT LTD

HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBRIDGE, MIDD.X.

Telephone: Uxbridge 5242

PIONEERS OF PRESTRESSED CONCRETE IN GREAT BRITAIN

STORERS

FOR

WM. T. STORER & CO. LTD., River Road, Barking, Essex, have been supplying softwood in London and the Home Counties since 1913.

Comprehensive Stocks are carried at the wharves, sheds and yards covering more than 10 acres.

Joinery Redwood from first-class Swedish productions is a speciality, but a full range of other grades from good Finnish and Swedish stocks is also offered.

Floorings and Matchings. Planed Boards, Mouldings, etc., are manufactured on the spot at short notice.

SOFTWOOD

Stock at one site only.
Modern Sawing and Planing Mill on the site.
Our own fleet of transport.

These all ensure prompt and personal attention to your requirements.

AND

INSPECTION WELCOMED


Telephone Rippleway 0301 (Ext 34)
and we will send car to meet you

SERVICE

PADIHAM 'B'

Power Station

NEAR BURNLEY



From the ground up . . .

First the foundations, now the superstructure of the main power house and ancillary buildings. Gleeson have been entrusted with providing both base and backbone of the new Padiham 'B' Power Station near Burnley.

Work in hand or recently completed, includes the following Power Station contracts.

Consulting Civil
Engineers
C. S. Allott & Son,
Manchester 3

Consulting
Architects
Cruikshank &
Seward,
Manchester

AGECROFT 'B'
CHAUDERTON
FLEETWOOD
CARRINGTON
WAKEFIELD

DRAKELOW 'B'
HIGH MARNHAM
BELVEDERE
WILLINGTON 'B'


GLEESON

Central Electricity Generating Board,
Northern Project Group,
Agecroft Road, Pendlebury,
Manchester.

M. J. GLEESON (CONTRACTORS) LTD.

Haredon House, London Road, North Cheam, Surrey.
Tel: Fairlands 4321/8 lines.


LONDON • SHEFFIELD • MANCHESTER



Architects :
S. N. Cooke & Partners
F./P.R.I.B.A.

Main Contractors :
William Townson & Sons
Ltd., Bolton.

Maxweld reinforces it



The reinforcement fabric used in the Metal Box Company factory at Bolton was supplied by Richard Hill. Do you need reinforcements? Then call up the Maxweld man! He can give you all the facts on the type and quantity of fabric you'll need plus a rough idea of the cost. And he's backed by the

Richard Hill Design Service

who can then draw up more detailed plans and estimates. You can get him at Middlesbrough (2206), London (Mayfair 3538), Birmingham (Mid. 5625), Manchester (Central 1652), Leeds (2-7540), Bristol (24977), Glasgow (Central 2179), Nottingham (Bulwell 27-8383), Bournemouth (Westbourne 63491), Cardiff (46552), Belfast (29126).

Maxweld fabric

is manufactured by **RICHARD HILL LIMITED** (Established 1888)

Newport Wire and Rolling Mills, Middlesbrough, Yorkshire. Tel: Middlesbrough 2206

A MEMBER OF THE FIRTH CLEVELAND GROUP



CRC II MX

Three is company



In modern construction the only way to be sure of 'smooth sailing' throughout a project is to have all the experts in at the start. Co-ordination at inception ensures efficient, economic and uninterrupted progress to prompt completion. This means that the contractor, with his wealth of practical experience in current constructional techniques and their specialised applications, must be on hand, together with the client and his consultant, at the planning stage to advise on design, materials and plant in relation to the specific requirements of each individual contract. Eliminate the chance of errors or omissions—modifications during construction are costly and difficult and cause expensive delays. Many clients make sure by availing themselves of Monk experience and 'know-how' from the earliest analysis.

Our resources are at your service, call on them now and insure against error or delay.




WARRINGTON & LONDON

A MONK & COMPANY LIMITED

Offices at Hull, Middlesbrough, Stamford

CIVIL ENGINEERING, BUILDING AND REINFORCED CONCRETE CONTRACTORS

Lillington's in the factory floors of another famous firm



Periodically Aveling-Barford Limited, of Grantham, who are the largest manufacturers in the World of heavy road rollers, dumpers, tractors and other agricultural machinery, extend their factories to meet the ever increasing demand.

It is essential that their concrete floors are waterproofed, case-hardened and dustless. To ensure these results, No. 1 Metallic Liquid is always added to the gauging water; a simple and inexpensive operation.

For nearly fifty years, architects have specified No. 1 Metallic Liquid, the scientifically prepared admixture that makes concrete completely waterproof and dustless as well as accelerating the setting time. No. 1 Metallic Liquid is a necessity for waterproof cement renderings to walls and basements, in mass concrete retaining walls, foundations, flat roofs and tanks. You can rely on Lillington's No. 1 Metallic Liquid to give complete satisfaction because **IT IS THE ONLY PROOFED SOLD UNDER GUARANTEE**

FROM **5/-** PER GALLON

Special terms for bulk contracts

Write for Booklet 56

**GEORGE LILLINGTON
AND COMPANY LIMITED**

Willow Lane, Mitcham, Surrey • Telephone: Mitcham 1066
For Scotland: 42 High Street, Greenock

AP/318A

ALL OUR PRODUCTS NOW SOLD IN FREE CONTAINERS

Lillington's
NO. 1 METALLIC LIQUID



An Electrically Driven PC3 Concrete Pump with remixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

FOR SALE AND HIRE

EFFICIENT RECONDITIONING SERVICE

CONCRETE BY PUMP AND PIPELINE

- The latest and most efficient method of placing concrete.
- Life of Pump practically indefinite : all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF




THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546

Telegrams: Pumpcret, Kens, London

MACALLOY*-the world over*

Docks, harbour works, bridges, dams in all parts of the world, use 'Macalloy' high tensile steel bars in prestressed concrete construction on the Lee-McCall system. The main illustration shows the Dock Reconstruction work employing 'Macalloy' bars at Mombasa Harbour, Kenya, East Africa.

PRESTRESSING
STEEL
by **McCALLS**

McCALLS MACALLOY LIMITED
TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex 8 lines)

LONDON: SLOANE 0428

BIRMINGHAM: ACOCKS GREEN 0229

McCALL & COMPANY (SHEFFIELD) LIMITED
McCALLS MACALLOY LIMITED
PRECISION ROOFS LIMITED

PORTSMOUTH: COSHAM 70702
NEWCASTLE: 30793

McCALLS MACALLOY AFRICA (PROPRIETARY) LIMITED
McCALLS MACALLOY (AUSTRALIA) PTY. LIMITED
McCALLS MACALLOY (CANADA) LIMITED
PC61

FOR CONSTRUCTIONAL PROJECTS OVERSEAS CONSULT CUBITTS

The Cubitt group includes established companies operating in various parts of the world — Anglin-Norcross Corporation Ltd. in Canada, Cubitt Wells Ltd. in New Zealand, Holland & Hannen and Cubitts (Middle East) Ltd. in the Middle East, and Holland & Hannen and Cubitts Ltd. in the West Indies. All these possess the important advantages of intimate local knowledge and long practical experience and are backed by the resources of a great constructional organisation which is fully equipped to undertake projects of any magnitude.


- Civil engineering projects of all kinds
- Complete factories with all electrical and mechanical services
- Structural engineering projects — with special experience of modern pre-cast pre-stressed concrete construction techniques
- Special contracts for installation of mechanical, electrical and other services
- Housing estates on the largest scale

CUBITTS

Great Britain, Canada, New Zealand, Middle East, West Indies

HOLLAND & HANNEN AND CUBITTS (GT. BRITAIN) LIMITED
ONE QUEEN ANNE'S GATE · WESTMINSTER, SW1

TGA C277R



**IN ONLY
24
HOURS**

Concrete with sufficient strength
for almost any purpose

WITH

'417' CEMENT

Extra-rapid-hardening—quick setting

The high strength attained by '417' Cement
within a few hours makes it invaluable for new concrete work
of an urgent nature and for repairs to roads, sewers,
railways, factories, etc. where it is vital there
should be no delay in completing
reinstatement of services.




Write for further particulars to:

THE CEMENT MARKETING CO. LTD.
Portland House, Tothill St., London, S.W.1
G. & T. EARLE LIMITED, Hull
THE SOUTH WALES PORTLAND CEMENT & LIME
CO. LIMITED Penarth Glam.



MODERNISATION OF MOTIVE POWER DEPOT, YORK



Arched ribs in Concrete Spanning 55 ft. on to framed steel beams 204 feet in length.

Completed section in foreground is of pre-stressed concrete beam construction bearing on in-situ columns and is glazed throughout.

Photographs by kind permission of British Railways.

For the design, manufacture and erection of concrete structures

consult

Concrete Services Ltd

OUSE ACRES · BOROUGHBIDGE ROAD · YORK · Tel. 76475

DEEP MINE CONCRETING SIMPLIFIED

**COLCRETE
INJECTED
CONCRETE**



COLGROUT mixing plant at a South African Gold Mine.



A station cross cut 6,000 ft. below surface, lined with Colcrete constructed from surface.

At South African Gold Mines the concrete linings of tunnels, pump chambers and the construction of shaft sumps have been simplified by using uncrushed rock spoil injected with COLGROUT mixed at surface and passed down shafts up to 6,000 ft. deep through 1½" pipes.

Contractors : The Cementation Company (Africa) (Pty.) Limited.



The main pump chamber of a South African Gold Mine 6,000 ft. below surface and lined with Colcrete.

Colcrete methods can solve many Concreting Problems

COLCRETE LIMITED


STROOD • ROCHESTER • KENT

Phone Strood 78431/2/3. Grams : Groutcrete, Rochester

'Visqu
laid un
floor m
at Ad
This
nation
buildi

Ge
at
da
F
sh
ad
th
TI
(se

Leading contractors defy damp with 'Visqueen' oversite membranes



'Visqueen' 500 heavyweight, laid under the concrete ground floor rafts of a Wimpey House at Acklam, Middlesbrough. This estate is part of their national speculative house building programme.

George Wimpey and Co. Ltd. insure against rising damp and sulphate attack on their housing estates. They specify polythene sheeting as a damp-proof membrane.

FIRST they put down a smooth concrete or sand blinding on the hardcore. Then the sheeting is quickly and easily unrolled. No adhesives or heat sealing are needed for the joints; just a simple "double welt" fold. The sheeting is incorporated with the d.p.c. (see diagram).

'Visqueen' building sheet is cheaper than

conventional oversite damp-proofing materials. It also provides an effective seal against liquids and is an efficient water vapour barrier.

'Visqueen' is flexible, tough and chemically inert. Its acid resistant qualities ensure lasting protection for floor coverings and adhesives.

For full details, an illustrated brochure and the name of your local 'Visqueen' distributor, write now to:


BRITISH VISQUEEN LIMITED

SIX HILLS WAY, STEVENAGE *A subsidiary company of Imperial Chemical Industries Limited*

CLIFTON BRIDGE Nottingham

includes the longest prestressed concrete span in Britain

No. 17 IN A
SERIES SHOWING
TECHNICAL DEVELOP-
MENTS IN CONCRETE
CONSTRUCTION



The new Clifton bridge has an overall width of 46 ft. 3 in. and its total continuous length, excluding the northern viaducts, is 800 ft. The centre span directly over the River Trent is 275 ft. long, with a span of 125 ft. on either side. Prestressing was by the Magnel Blaton system.

* Johnsons have had a share in many advanced prestressed concrete projects, in this country and overseas. Write for our illustrated brochure which gives details of many of these outstanding contracts.

Sponsor :

City of Nottingham
City Engineer and Surveyor :
Mr. R. M. Finch, O.B.E., M.I.C.E.

Consulting Engineers :

R. Travers Morgan & Partners

Contractors :

James Miller & Partners Ltd.,
18-20 George St., Edinburgh, 2.

Ever since prestressed concrete construction was first used in this country, designers, architects and civil engineers have specified 'Wire by Johnsons'. The reason is quality, built up on early experimental work with those specialist designers who studied and worked in the Continental Development of this new building technique. Johnsons have a long record of 'Firsts', including indented wire for greater bonding and coils of 8 ft. diameter from which the wire pays out straight.

wire was essential -

Johnsons

of course!

Underreamed Bored Piling

McKinney Foundations
Limited specialise in the
drilling of

 **ALREADY IN OPERATION
A LARGER DRILLING RIG
GIVING DEPTHS TO 110 FT.**

with modern heavy duty
mobile plant and equipment.

Foundation borings varying from one to eight feet in diameter (or more in special cases) can be drilled and their bases can be underreamed so as to flare out and provide a substantial bearing area.

Because of the speed and economy of this method, foundations may be taken down to depths which allow better load bearing at no extra cost.

Advisory Service

Advice on foundation design and construction is available and you are invited to write or telephone:

**McKINNEY FOUNDATIONS
LIMITED**

Manor Way, Boreham Wood, Hertfordshire. Telephone: Elstree 2854.

NOW! SLASH LABOUR AND TRANSPORT COSTS ON SLAB SHUTTERING WITH THE

MILLS

pecco-beam



- * Proven safety factor 2.2:1
- * Lightning adjustment from 8' 6" to 27' 7"
- * Unique *one-stroke* wedge lock
- * Makes propping obsolete
- * Free work areas for kindred trades below
- * Two basic components: lattice section and plate section
- * Immediate delivery from nearest **MILLS** depot

**The new all-steel
eliminates propping**

LOWEST EVER LABOUR COSTS EVER

Here's the quickest, easiest and safest shuttering support ever devised—the Mills Pecco-Beam.

In minutes, the components can be telescoped any span between 8' 6" and 27' 7". The span locked with a steel wedge—rammed home with one blow of a hammer—and beams are ready hoist into position. There are no loose parts; no screws to burr; and the timber cutting at intermediate propping required for conventional shuttering is eliminated. Kindred trades can work unhindered in the area below.

FREE PLANNING SERVICE Mills Drawing Office provides a free planning service to users of the Pecco-Beam. Also a six page leaflet, containing a loading table and details of the Beams, is available from your nearest Mills Depot.

THERE'S NO LIMIT TO THE SUPPORT

WHY
GIVE
AND


The pla
steel r
drawin
length
single
Pecco-
torque
are po
tenanc
becau
LOA
PECC
YOU
LARG
FEW

SSU
op be
iled-i
ving
eel is
main
ten u


rusley
epots:
ristol - G
ull - U
ewcast
ortamo

WHY MILLS pecco-beam GIVES MAXIMUM STRENGTH AND SAFETY


The plate section of the Pecco-Beam is a strip of steel moulded to a 'V' shape (see head-on drawing) so the steel is 'doubled' along the length of the beam, instead of being only a single strip as on some other plate sections. The Pecco-Beam has a high degree of horizontal and torque stability. On site considerable savings are possible in transport, maintenance and labour costs, because—THE GREATER LOAD CAPACITY OF PECCO-BEAM MEANS YOU CAN SHUTTER LARGER AREAS WITH FEWER SHORES.



Unique wedge-lock secured at one hammer blow. Adjustment made positive by a combination of camber and load.



Bearing prongs are drop forgings, welded to beams. Dove-tailed to avoid overlapping.



horizontal shoring which
span up to 27' 7"


LEVEL SLAB ASSURED UNDER LOAD

Top bearing sections of the Pecco-Beam have a built-in camber. This levels out under load giving a flat surface, but because high grade steel is used to make the beams, the camber remains unaffected even after the shoring has been used hundreds of times.

MILLS SCAFFOLD CO. LTD.

(A subsidiary of Guest, Keen & Nettlefolds, Ltd.)

Works, Hammersmith Grove, London, W.6 (Riverside 3011)
Branches: Birmingham · Bournemouth · Bradford · Brighton
· Bristol · Canterbury · Cardiff · Coventry · Croydon · Glasgow · Hastings
· Hull · Ilford · Liverpool · London · Manchester · Middlesbrough
· Newcastle · Nottingham · Oxford · Preston · Plymouth
· Portsmouth · Reading · Rotherham · Southampton · Swansea



VARIOUS BEAM COMBINATIONS

Pecco-Beams have two lattice sections, one 8' 6" long, the other 11' 10" long. The plate section is also 8' 6". Spans from 8' 6" to 27' 7" can be obtained by alternating the types of beams used.

YOU CAN GET FROM

MILLS

Testing concrete cubes on site


MILBANK-WELLS

HYDRAULIC PRESS AND CUBE MOULDS

Immediate Delivery

Two Sizes : 4 in. and 6 in.

PRESSES and CUBE MOULDS
Testing to 16,000 lb. per sq. in. to
B.S. 1881.



Approved for
all Government
Contracts

IN USE
ALL OVER
THE WORLD

6-IN. PRESS
258 TONS

£235

4-IN. PRESS
110 TONS

£120

MILBANK FLOORS LTD


PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX

Telephone: Earls Colne 410




PRESTRESSED FLOORS & ROOFS SPANS UP TO 40 ft.
FRAME BUILDINGS ALL TYPES



THE MOST ADAPTABLE FRAME BUILDINGS
FOR INDUSTRY AND AGRICULTURE

SINGLE SPAN · MULTI SPAN · CANTILEVER



**ISLE OF GRAIN
BRADWELL
GATWICK**

At the Isle of Grain Refinery for the British Petroleum Company Limited, Bradwell Nuclear Power Station and Gatwick Airport, Sternson No. 610 was used.

Sternson No. 610 is the obvious choice. Not only for bonding granolithic topping but for ensuring watertight construction joints. And the bonding


of heavy renderings to concrete surface without hacking.

Used on many Government Contracts at home and overseas, in the multi-storey John Lewis Building in Oxford Street, in Bowater House, the Walls Depot at Acton . . . The list is almost endless. Using Sternson No. 610 puts you in good company.

CONCRETE BONDED WITH "Sternson" 610

SBD
STUART B. DICKENS LTD.

For complete information, write :—
Manor Way, Boreham Wood, Herts.
Telephone : Elstree 2211.



PRECAST HOLLOW FLOORS & ROOFS

Shockcrete Units are being used extensively for Schools, Flats and Industrial Buildings. Manufactured under factory conditions by advanced techniques, they can be speedily erected by our own labour force.

Shockcrete Units are:

- QUALITY CONTROLLED AT EVERY STAGE
- ECONOMICALLY PRODUCED TO CP114 (1957)
- DELIVERED TO CONTRACT WITHOUT FAIL

A skilled and experienced staff of Engineers and Designers are available to undertake design and layouts for Clients, and co-operate at every stage until completion of contract.



Call in

SHOCKCRETE

PRODUCTS LIMITED


RYE HOUSE WORKS HODDESDON
HERTS. HODDESDON 3037

Also for Precast Concrete Piles and
Tunnel Linings

ONE...



TWO!



'STABIL' BINDERS ARE GREAT LABOUR SAVERS

In one simple action they fix reinforcing rods as though welded. No slipping. No "fiddling" with wire. No tools to get mislaid. Any workman can use them. Made in all sizes for binding $\frac{1}{4}$ -inch up to $1\frac{1}{2}$ -inch rods. Give "Stabil" Binders a trial and judge for yourself.

- SEND TO-DAY for demonstration samples and prices.

HUNTLEY & SPARKS LTD

DEBURGH RD., S. WIMBLEDON, S.W.19

Phone: Liberty 2446

BIGGEST AND WIDEST RANGE EVER OF CARBIDE TIPPED DRILLS!

Pioneers in carbide tipped masonry drills, the Rawlplug Company has gone still further ahead with the widest range of percussion, vibration and rotary drills

obtainable anywhere. Whether it's for hand or power use, you're bound to find the type and size you want in the Rawlplug range.

'DURIUM' TIPPED MASONRY DRILLS

So famous have these amazing drills become that the name DURIUM tends to be used for any drill of its general type. *Don't be misled by this.* DURIUM means the special New Process, almost diamond-hard, carbide tip developed and made only by the Rawlplug Company. No other drill is a genuine Duriium. DURIUM Drills give really sensational cutting performances in brick, tile, cement, slate, etc. They are silent in operation and have a quite exceptional long-service capacity for withstanding the abrasive action of masonry that so quickly ruins ordinary drills. Another exclusive feature of Duriium Drills is their patented rapid-helix flute, which forces out spoil and prevents clogging. Only a Duriium Drill—a genuine Rawlplug Duriium—gives such life and service. First resharpening is FREE

For use in Wheelbrace or slow speed electric drill
17 sizes 5/32" to 1" cutting diameter and 11 long series
1/2" to 1" cutting diameter for up to 16" drilling length.




'VIBROTO' HARD TIPPED DRILLS FOR VIBRATORY DRILLING

Vibroto Drills are specially manufactured for use with the Vibroto Drilling Machine, —a high efficiency power tool which allows of two vibratory actions (Light Rapid and Heavy Slow), and also a rotary action for use with standard Duriium masonry Drills or ordinary Twist Drills. With their special cutting angle metallic carbide tips, and the high grade steel shanks heat-treated to withstand abrasion, Vibroto Drills put up spectacular performances in the drilling of concrete and other hard materials. Demonstrations can be carried out by Rawlplug Technical Representatives anywhere in the British Isles.

10 sizes 5/32" up to 15/32" cutting diameter.



'DURIUM' TIPPED HAMMER DRILLS



For percussion drilling in hard materials such as Granite, Blue Bricks, Concrete etc., Duriium Hammer Drills have a very much longer life than ordinary percussion drills. They can be used in most electric Hammers and some type of Pneumatic Hammers. 13 sizes from 7/16" nominal drill diameter to 1 1/2".

'DURIUM' TIPPED GLASS DRILLS

For use in glass, china, vitrolite, pottery, etc. Can be used in a wheelbrace or slow speed electric drill.
9 sizes from 1/4" to 3/4" cutting diameter.



'RAWLCRETE' TUNGSTEN CARBIDE TIPPED (ROTARY) CONCRETE DRILLS

These drills are designed for hole boring in concrete, hard brickwork and tiles with portable rotary action tools. They have from four to six cutting edges (depending on size) and if one should be damaged the remainder will go on cutting. Spoil is automatically carried away through the cored shank and ejected via the slot.

EXTENSION TYPE DRILLS ANY DEPTH
By adding extension rods to the Extension Type Rawlcrete Drill, any depth of hole can be drilled.
26 sizes 1/4" up to 2" cutting diameter.



RAWLPLUG FIXING DEVICES AND TOOLS FOR SPEED AND RELIABILITY

WRITE NOW

for illustrated literature describing fully these and other Rawlplug high performance drills and power tools.




THE RAWLPLUG COMPANY LTD.
CROMWELL ROAD, LONDON, S.W.7.

Telephone: FREMANTLE 8111 (10 lines)

Telegrams: RAWLPLUG SOUTHKENS LONDON

The World's Largest Manufacturers of Fixing Devices



For compacting mortar cubes
for compression tests to
B.S. 12/1958, 146, 1370, 915
Automatic Time Control

"CAPCO"

H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical
Moulds; Compacting Factor Apparatus—Standard and Auto-
matic; Sieve Vibrators and Sieves; etc.

CAPLIN ENGINEERING CO. LTD

ALPAX WORKS, ST. LEONARDS ROAD, WILLESDEN JUNCTION, LONDON, N.W.10
*Phone: ELGAR 7191. Grams: CAPLINKO, London, N.W.10. Cables: CAPLINKO, LONDON



BOLTS & NUTS

TIE-RODS

ETC.

**FOR THE
CONTRACTOR**



Manufactured by

B. PRIEST & SONS LTD

OLD HILL · STAFFS · ENG.


PHONES: CRADLEY HEATH 6227 · 8 · 9 & 6220

VIBRO Cast-in-place PILES support tallest building in Cairo

The "Daira Zalzal" building constructed at Garden-City on the bank of the river Nile is the tallest building in Cairo. This 31-storey block stands on 310 Vibro cast-in-place reinforced concrete piles varying in length from 33 to 50 ft., with a working load of 60 tons per pile.

An even taller block, the 36-storey "El Tewfick" building, also founded on VIBRO Piles, is now in course of erection.

Write for list No. 192



TECHNICAL REPRESENTATIVES THROUGHOUT THE WORLD

THE BRITISH STEEL PILING CO. LTD.

10 HAYMARKET, LONDON, S.W.1.

Telephone: TRAfalgar 1024

WOOD MOULDS

for PRECASTING

EXTREME ACCURACY

ALL TYPES | **ALL SIZES**

25 years' experience at your service

ARCHITECTURAL SPECIALISTS
AND MODEL MAKERS

LAWS & SON (STAINES) LTD
(CONTRACTORS TO H.M. GOVERNMENT)

Langley Road Works, Staines, Middx.

Telephone : Staines 3700



- FOR
- BUILDING
 - HORTICULTURE
 - INDUSTRIAL USE

POLYTHENE

POLYTHENE SHEETING
IN CONVENIENT 20-YARD ROLLS

150 GAUGE CLEAR

48" Wide	11/- Roll
72" Wide	16/6 Roll
96" Wide	22/- Roll

200 GAUGE CLEAR

48" Wide	14/9 Roll
72" Wide	22/- Roll
100" Wide	31/- Roll

500 GAUGE CLEAR

48" Wide	36/9 Roll
72" Wide	56/- Roll

SPECIAL LIGHTWEIGHT

48" Wide	7/- Roll
----------	----------

BLACK SHEETING

48" Wide 100G.	12/6 Roll
----------------	-----------

Trade Enquiries Invited

12 ft. WIDE SHEETING

150 Gauge 900 ft. Roll	475/-
200 Gauge 800 ft. Roll	430/-
500 Gauge 250 ft. Roll	440/-

CARRIAGE PAID on orders over
£5; Orders up to £1 add 2/- Del.
£2, 3/6; £3, 5/-

POLYTHENE BAGS— Special Lightweight

8 x 19	8/6 per 100—88/- 1000
8 x 14	9/6 " " —61/8 1000
10 x 19	9/9 " " —52/2 1000
10 x 16	11/- " " —74/- 1000
10 x 18	12/- " " —94/6 1000

LARGER SHEETS UP TO SIZE 36 ft. x 60 ft. Prices on Request.

T.P. POLYPLASTIC CONVERTERS LTD

(Dept. RD.21) 672 FULHAM RD., S.W.6. (RENOVN 2277/5557)

Best Quality
**CONCRETE
AGGREGATES**
in all grades

DELIVERED BY ROAD OR RAIL

WM. BOYER & SONS LTD

MEMBERS OF S. & G.A. of G.B.

ESTABLISHED 1810


IRONGATE WHARF, PADDINGTON, W.

TELEPHONE : PADDINGTON 2024-6

TABLES FOR THE DESIGN OF BEAMS AND SLABS ACCORDING TO B.S. CODE OF PRACTICE No. 114, 1957

In response to many requests, the article and tables by Mr. Jacques S. Cohen, in this journal for August, 1957, have been reprinted together with an additional table. These tables enable any rectangular section to be quickly designed by both the elastic method and the load-factor method, and the relative economy of the results of each method of design can be seen at a glance. The price of the reprint is 4s. (4s. 3d. by post); 1 dollar in Canada and the U.S.A.

CONCRETE PUBLICATIONS, LTD., 14 Dartmouth Street, London, S.W.1



POWER for industry

Our range of industrial engines are a practical proposition for many types of industrial equipment... compressors, cranes, pumps, contracting equipment, earth borers, generators, railcars, welding plant, works trucks, tractors and conversions. Simple design, modern flow-line production methods and common interchangeable parts contribute to the low cost of these high efficiency engines. And remember, every engine is fully backed by a World-wide Parts and Service Organ-

sation. Take your choice from a wide power range... Diesel 20 to 86 b.h.p. and Petrol 11 to 87 b.h.p. (12-hr. rating).

DIESEL ECONOMY—have you considered the replacement of existing power units in your equipment and trucks with the famous 4D Diesel engine? You'll have the unique advantages of economy, long-life and low running costs... plus the best service in the World!

Wherever you are, whatever your problem,



**MOTOR COMPANY LIMITED
ENGLAND**

are at your service

For further details of our

INDUSTRIAL ENGINES

and the equipment they power,
send the coupon to your nearest Ford Dealer
or direct to

Please send me technical brochures of your
*PETROL/DIESEL Industrial Engines. The
maximum R.H.P. required is.....at.....
R.P.M. Also, please send details of the follow-
ing equipment powered by your engines.

Name.....

Address.....

Nature of Business.....

Telephone No.

* Delete where not applicable

G51-23-12

CONCRETE PROOFING Co. LTD.

GUNITE SPECIALISTS

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request

116 Richmond Road, Kingston-upon-Thames, Surrey. **KINGSTON 7883 and 9237**

Telephone:

WELBECK TRADING Co. (London) Ltd

WELBECK HOUSE, 2-6 BACHES STREET, CITY ROAD, LONDON, N.1

Telephone: CLerkenwell 4373 (PBX)

Telex: 23712


STEEL REINFORCEMENT MANUFACTURERS

$\frac{3}{16}$ " to $\frac{9}{16}$ " DIAMETER ROUNDS

Cut to dead lengths a speciality

No extra for cut lengths over 5 feet

Bending if required



Write or telephone your requirements

On A46 the Thurmaston By-Pass of twin-road construction has special reinforcement by McCalls to the recommendations of the Road Research Laboratory. The road is a pilot scheme for the Grantham by-pass and is being constructed by the Direct Labour Dept. of the Leicester County Council.



CONCRETE ROADS FIRST because CONCRETE ROADS LAST



A46

THURMASTON BY-PASS

**REINFORCEMENT
by McCALLS**

McCALL & COMPANY (SHEFFIELD) LIMITED

TEMPLEBROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex. 8 lines)

LONDON: SLOANE 0428

BIRMINGHAM: ACOCKS GREEN 0229

McCALL & COMPANY (SHEFFIELD) LIMITED

McCALLS MACALLOY LIMITED

PRECISION ROOFS LIMITED

PORTSMOUTH: COSHAM 78702

NEWCASTLE: 38793

McCALLS MACALLOY AFRICA (PROPRIETARY) LIMITED

McCALLS MACALLOY (AUSTRALIA) PTY. LIMITED

McCALLS MACALLOY (CANADA) LIMITED

Reinforced Concrete
DESIGN AND CONSTRUCTION

Cast Stone
AND PRECAST CONCRETE

Floors
IN SITU AND PRECAST

Granolithic Pavings

Staircases
IN SITU AND PRECAST

STUART'S

GRANOLITHIC CO. LTD.

FOUNDED 1840

LONDON

14 College Road, Harrow, Middlesex.
Telephone: Harrow 6161/2.

EDINBURGH


46 Duff Street.
Telephone: Edinburgh 61506.

BIRMINGHAM

Northcote Road, Stechford.
Telephone: Stechford 3631/2.

MANCHESTER

Ashton Road, Bredbury, Stockport.
Telephone: Woodley 2677/8.



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

* We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone: 3385-6

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENsington 3583

For Greater Strength, Firmer Bonding
and Better Surfacing of Concrete—

"BAXTUL"

Regd. Trade Mark *British Made*

**Extra-High Frequency
INTERNAL CONCRETE VIBRATORS**

● The model illustrated here operates at 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.

● Petrol or Electric Drive.

● Robustly built throughout and backed by genuine service.

● Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for: SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood).

one yard – or hundreds

from a small transportable concrete batching and central mixing plant



Photograph by kind permission of Stamford Construction Ltd.

MILLARS'

will be happy to supply details on the above 'Universal' set-up, which is one of the handiest, most economical and up-to-date plants yet designed for the production of dry-lean and quality concrete, or for the batching of truck mixers.

Ask also for information on other batching and central mix plants, the Millars' range of mixers, wellpoint dewatering system and asphalt and coated macadam plant.

MILLARS' MACHINERY CO. LTD

Licenses of the Vacuum Concrete, Rheax sand classification and Prepakt concrete grouting processes.


Head Office: Pinners' Hall, Great Winchester Street, E.C.2. Tel: London Wall 4266/9

Works: Bishop's Stortford, Herts. Tel: Bishop's Stortford 694/5

ABELSON *for SKIPS*




Circular tipping skips 2½ cu. ft. to 3 cu. yd.



Concrete pouring skip side discharge 10 cu. ft. to 2½ cu. ft.




Circular controlled discharge bottom dump skips 1 cu. yd. to 1 cu. yd.



Square tunnelling or trenching skips 4-25½ cu. ft. capacity.



Rollover skips ½ cu. yd. capacity.



Boat skips 3 cu. ft. to 7 cu. ft.



Concrete pouring skips bottom discharge 10 cu. ft. to 27 cu. ft.

Special and non-standard skips manufactured to your specifications.

ABELSON
& CO. (ENGINEERS) LTD.

SHELDON
BIRMINGHAM 26
TEL. SHELDON 2424 (10 lines)

GUNITE SPECIALISTS

W.M. MULCASTER

& CO. (CONTRACTORS) LTD.


We invite inquiries for Gunite Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON


CREWE

Telephone: Crewe 2265-6.

Bridge Bearings by WESTWOODS



All types supplied,
including multiple
roller bearings with
rockers, single
roller bearings,
rocker bearings
and hemispherical
bearings.



JOSEPH WESTWOOD & CO. LTD.

Contractors to H.M. Government Departments, Crown Agents for the Colonies, British Railways (British Transport Commission) etc.
etc. Bridge and Constructional Engineers, Manufacturers of Mechanical Grabs, Pressed Steel Troughing and Sheet Metal Equipment.
Steel Stock Holders.

NAPIER YARD, MILLWALL, LONDON, E.14. Tel.: EASt 1043

There's no substitute for EXPERIENCE



Introduced 11 years ago, a quarter of a million Land-Rovers are now in action all over the world ... tackling the toughest assignments in all conditions and all climates. There can be no greater tribute to Rover engineering than the world-wide reputation which Land-Rovers have won for reliability and endurance.

ONLY LAND-ROVER OFFERS YOU:

- ★ 11 years' practical experience in the go-anywhere, do-anything field.
- ★ A choice of chassis lengths—Regular or Long.
- ★ A choice of engines—Petrol or Diesel.
- ★ A choice of 10 body styles in lightweight, rust-proof alloy.

*Ask your Distributor or Dealer
for a Land-Rover demonstration.*

Prices from £650

***There's no substitute
for the 4-wheel drive***

**LAND-
ROVER**

**PETROL
or
DIESEL**



*Regular Land-Rover—
hard top*



*Long Land-Rover—
truck cab*



RYLANDS

Prestressed concrete wire for New Zealand!



Consultants:
Prestressed Concrete N.Z. Ltd.
Contractor:
Wilkins-Mason Ltd.

One of two large digesters under construction for the Auckland Metropolitan Drainage Board Project. This unit is being constructed in pre-stressed concrete using Rylands Standard Stress Relieved Wire. Tensile strength 100/110. Sizes used were .276" diameter and .200" diameter.

RYLANDS

Brothers Ltd

WARRINGTON
ENGLAND

"COL-O-ROCK"

Registered Trade Mark

EXPOSED-AGGREGATE PANELS

by

J. A. KING & Co., LTD

Write or Phone

181 Queen Victoria St., LONDON, E.C.4


Telephone: CENTral 5866 (5 lines)

Telegrams: Kinovique Cent London

COPPER STRIPS

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.




ALEX J. CHEETHAM LTD.

MORTON STREET • FAILSWORTH • MANCHESTER

Telephone: FAIlsworth 1115/6

DS.14



333 Simplex Cast-in-situ Concrete Piles were used in the foundations of the Municipal College Extensions in Anglesey Road, Portsmouth

Architect to the City of Portsmouth: F. Mellor, Esq., F.R.I.B.A.

SIMPLEX CONCRETE PILES LTD.

190 PALACE CHAMBERS,

BRIDGE STREET,

WESTMINSTER, S.W.1

Telephone: Trafalgar 1167-9



By courtesy of the
Nuclear Power Plant Co. Ltd.

use Thames **NOILPLY**

—a non-oil plastic-faced shuttering used by Sir Robert
McAlpine & Sons Ltd. at the Bradwell Nuclear Power
Station of the Central Electricity Generating Board.

Thames Noilply Shuttering is faced on one side with an impervious gloss tough plastic *which can be used up to 80 times without oiling*. The reverse side is balanced with a standard plastic.
80 uses per board represents a useful saving of both oil and labour. In fact the use of 'Noilply' will quickly repay its extra cost (26s. per 100 sq. ft. more than Thamesply standard plastic-faced shuttering). Even after use as non-oil shuttering the shutter *will still have a useful life for general shuttering purposes*. The 'Noilply' Shutter demands no better treatment than any other good shutter.
Why not try 'Noilply' on your next contract?



Supplied only through the usual trade channels.

Thames Plywood Manufacturers Limited
Harts Lane, Barking, Essex. Telephone: RIPpleway 5511


FOR CONCRETE PRODUCTS

Invest in

RANALAH

**STEEL
MOULDS**

**CUT CAPITAL COSTS
BETTER CASTS & MORE
CASTS PER MOULD**



**GARAGES, COAL BUNKERS, CILLS,
COPING STONES, AGRICULTURAL AND
INDUSTRIAL BUILDINGS, FENCING POSIS,
KERBS, GARDEN EDGING, ETC.**



RANALAH STEEL MOULDS LTD

LOWER BEVENDEAN

BRIGHTON

SUSSEX TEL: 62216-78

Steel Reinforcement

A complete service of
Design, Fabrication and
Fixing of Steel Rein-
forcement for all types
of Reinforced Concrete
Construction.

M.S. Bars to B.S.S. 785, bent,
bundled and labelled, delivered to site
ready for fixing. No loss of time in
checking and sorting material. No
loss of material due to prolonged
storage on site.

T. C. JONES

AND COMPANY LIMITED

REINFORCEMENT ENGINEERS

17 BUCKINGHAM PALACE GARDENS
LONDON, S.W.1 Tel: SLOane 5271

Head Office: Wood Lane, London, W.12


Tel: Shepherds Bush 2020

South Wales Office: Bute Street, Cardiff

Tel: 28786

Works: Shepherds Bush, London. Neasden, Middx.
Treorchy, Glam.





..... *thinking of rooflighting?*

or any other glass and ferro concrete structure, for that matter.

Lenscrete Limited can provide the answer.

The two pieces of literature illustrated provide useful information and technical data on all types of natural lighting for buildings. Details are given of Lenscrete's comprehensive range of translucent concrete construction and fibreglass, perspex and glass roof domes and metal ventilators.

Lenscrete Limited will be pleased to send you this literature on request.

Send for this catalogue ▶



LENSCRETE LTD

QUEEN'S CIRCUS LONDON SW8 Telephone: MACaulay 1063

WATERTIGHT

LININGS

FOR

RESERVOIRS,

SWIMMING

POOLS, ETC.



LININGS

FOR

TUNNELS,

SEWERS,

TANKS.

*Specialists in the Repair and Reconditioning of
Reinforced Concrete Structures, etc.*

THE

GUNITE
CONSTRUCTION CO. LTD

WESTERN HOUSE, HITCHIN, HERTS.

Telegrams :

Gunite

Hitchin

Telephone :

Hitchin

4371

CUT YOUR CONCRETE COSTS

with the

A.B. MOULD MIXER-DRIVE SHOVEL


ALL BRITISH DESIGN AND MANUFACTURE

(Patent applied for)

At last !

The perfect combination of a winch unit attached to and driven by the mixer, but operated from the press-button-controlled shovel.

**THE BUILT-IN JIB ELIMINATES
SITE INSTALLATION COSTS.**



**LOW CAPITAL OUTLAY RECOVERED IN TEN WEEKS
NO RUNNING COSTS
FITTED TO MOST MIXERS**

Ask for a demonstration from :

A. B. MOULD & CONSTRUCTION CO., LTD.

**VULCAN WORKS, VULCAN WAY
NEW ADDINGTON, SURREY**

Telephone : Lodge Hill 2347

Telegrams : Abmould, Croydon

ACHIEVEMENTS IN BUILDING

CONTRACT

COMPLETED

8 MONTHS

AHEAD OF

SCHEDULE



MULTI-STOREY FLATS FOR
L.C.C., SQUIRRIES STREET,
BETHNAL GREEN

Clients:
The London
County Council
Architect of the Council:
Hubert Bennett, F.R.I.B.A.
Architect in Charge:
A. E. Long, A.R.I.B.A.
Principal Housing Architect:
H. J. Whitfield Lewis, A.R.I.B.A.

Photo by ARCHIE
HANDFORD LTD.

How is it done? By Planning that covers every detail before work is begun, the approach to all R & T projects. By virtue of close co-operation between Client, Architect and Rush & Tompkins, with their

expert knowledge of building techniques, all problems are resolved in advance, with the resultant saving in time and money.

R & T are worth remembering

R

T

RUSH & TOMPKINS LIMITED

BUILDING & CIVIL ENGINEERING CONTRACTORS

SIDCUP • LONDON • DURBAN • EDMONTON, ALBERTA

Precision in Concrete Cover...



Write Now!

for fully
illustrated
brochure

A revolutionary economy
for lightness, speed of
handling, and range of
application—for reinforcing
bars in concrete.

with



PATENTED. Regd. Design 893503.

Plastic Distance Pieces



Samuel & Son (moulders) Ltd

WREN MILL, CHADDERTON, LANCS. Sales Office: Tel: Manchester DEA 4671/2
Sole Manufacturers and Distributors of ABIT pk Plastic Distance pieces (A.B.
ABERG No. 31269/58) in Great Britain, The Commonwealth and Eire.

STRAND OR WIRE STRESSING

PRE- AND POST- TENSIONING

Here is an economical and portable stressing set of high quality. Interchangeable components enable the same jack to be used for stressing wire or strand.



Three standard forms are available:

1. For 3/8" and 7/16" diameter strand.
2. For 0-128", 0-200" and 0-276" diameter wire.
3. For both wire and strand.

The jack works in conjunction with an instant-release grip, which permits rapid change-over on multiple work, and caters for long extensions (a second or third bite can be commenced within seconds of reaching maximum jack travel).

The set comprises self-retracting 6" or 12" extension jack, hand pump, pressure gauge, 6' length flexible hose with quick couplings, instant-release grip and jaws. These are all contained in a stout wooden box from which the pump may be operated without removal.

U.K. Ex-Works prices as follows:

	6" extension	12" extension
Complete Set for Strand Stressing	£95	£115
Complete Set for Wire Stressing	£87	£107
Complete Set for Both Wire and Strand	£114	£134
Conversion Set Strand to Wire	£19	
Conversion Set Wire to Strand	£27	

Send for our new booklet covering both pre- and post-tensioning.

STRESSING DEVELOPMENTS LTD.

95 KINGSTON HILL, KINGSTON-UPON-THAMES

TELEPHONE: KINGSTON 2372

**1574
pages**

containing details of the experience
of engineers of many countries
in overcoming the problems of

CONCRETING IN COLD WEATHER

A SYMPOSIUM ON WINTER CONCRETING

held in Copenhagen
in 1956 under the
auspices of the
Danish National
Institute of Building
Research.

This volume of 1,574 pages, printed in the English language, gives the papers read at the RILEM Symposium on Winter Concreting, in which engineers from many countries give the results of their experience in successfully carrying out concrete work at very low temperatures.

Full accounts are given of the methods used in Sweden, U.S.S.R., China, Japan, Poland, Finland, India, and other countries, and some papers describe laboratory work on this subject.

In addition to the papers, the important contributions to the discussions are included, so that the volume describes the practice and gives the opinions of some 50 of the world's most experienced engineers on this subject.

Summaries of the main conclusions reached are printed in the English, French and German languages. Authoritative information is given on the effect of using high-early-strength cement, air-entraining calcium chloride, electrical heating and curing, steam heating and curing, heated mixing water, ready-mixed concrete, and all other means of preventing damage by frost.

This volume is the most exhaustive and valuable treatise on concreting in cold weather yet published in the English language. Obtainable by sending the order form below to the Selling Agents.

ORDER FORM


To **CONCRETE PUBLICATIONS, LTD., 14, DARTMOUTH STREET
LONDON, S.W.1, ENGLAND.**

Please send to the address below.....copy (copies) of the RILEM Symposium on Winter Concreting. A remittance for *..... is enclosed.

**BLOCK LETTERS
PLEASE**

NAME.....
ADDRESS.....

* Price 65s. ; by post 67s. 12.50 dollars in North America.



**200
cycles**

ALLAM

INTERNAL VIBRATORS without flexible drives

Now fitted with overload and anti-single-phase switches.

This new internal vibrator dispenses with the use of flexible drives. It has a frequency of 12,000 r.p.m. which, combined with amplitude, provides exceptional compaction of very harsh mixes. Vibrators of varying sizes, together with single- and multi-tool generators (Petrol, Diesel, and Electric drives), make this the most versatile range of internal vibrators so far available. It is in full production, and has already proved of considerable value to Contractors, Builders, and Precast Concrete Makers. Complete details of these and the range of Allam Vibrating Equipment will be sent on request.

E · P · ALLAM & CO. LTD.

LONDON: 132-135 Sloane Street, S.W.1. • Telephone: Sloane 9976 (5 lines)

Works: Southend-on-Sea Tel.: Eastwood 525243

AGENTS & DISTRIBUTORS: Strangford Ltd., Belfast and Dublin; A. Gunn & Co. Ltd., Altrincham, Ches.; O. L. Davies Ltd., Port Talbot, Glam.; J. Lewis (Machinery) Ltd., Burslem, Stoke-on-Trent; G. B. Corner & Son, Leeds and Nottingham; John Roulstone Ltd., Newcastle-on-Tyne; W. R. Selwood, Ltd., Chandler's Ford, Southampton; J. A. McAra & Co. Ltd., Glasgow.



The finest portable silos in the world

FOR HANDLING CEMENT IN BULK

P15 PORTASILO working on the construction of Wilmslow Grammar School, Cheshire.
Contractors: L. Brown & Sons Ltd. Wilmslow

- ✱ Fully proved on thousands of sites
- ✱ A range to suit all Concrete Mixers
- ✱ No condensation problems
- ✱ Backed by a first class after sales service
- ✱ Fully automatic, remote push button control provided by the addition of the Portasilos 'Autofeed' which can be interchanged between Portasilos as required
- ✱ FOR SALE OR HIRE



PORTASILO LIMITED


CONTRACTORS PLANT DIVISION, CORONATION ROAD, PARK ROYAL, LONDON N.W. 10
Telephone: ELGAR 6214 - 6215 - 3726

HEAD OFFICE: YORK
AND AT BIRMINGHAM, MANCHESTER, GLASGOW, BRISTOL, BELFAST AND DUBLIN

Write or phone today for details of full range of 11, 15, 20 and 30 ton capacity models or ask for a representative to call

A TRICOSAL TIME-TESTED JOB

**The
Mersey
Tunnel**



FLOROSAL

for Surface Hardening and
Protection of Concrete, Stone
and Cement.

NEOCOSAL

for Surface Waterproofing of
Brick, Concrete and Stone.

Send for Information Leaflet No. 1

**A. A. BYRD & CO. LTD., Dept. C., 210 Terminal
House, Grosvenor Gardens, London, S.W.1.**

Phone: SLOane 5236 Grams: Byrdicom, Westphone, London
Works: Basingstoke, Hants.

When, in 1934, they mixed the cement and sand rendering for lining the famous Mersey Tunnel, Tricosal was added to increase its hardness and waterproofing properties. The $\frac{3}{4}$ " thick rendering covered an area of 80,000 sq. yds. The work was done by the Gunité specialists Concrete Proofing Co. Ltd., and 25 years later is as good as on the day it was done.



**An Osal Product
INDISPENSABLE FOR CEMENT WORK**



PIERHEAD

**PRECAST
PRESTRESSED
CONCRETE UNITS**

FOR FLOORS & ROOFS


Pierhead standard prestressed
flooring structural units are
manufactured in lengths
up to 42 ft.

FOR BRIDGES

Pierhead standard beams
for spans from 10 to 60 ft.
result in great economy

Pierhead Bridge Beams Brochure
or Pierhead Flooring Brochure
forwarded on request

design | supply...



erect

PIERHEAD LTD.

SPEKE BOULEVARD, LIVERPOOL 24. Tel. Hunts X 1311
FAGGS ROAD, FELTHAM, MIDDLESEX. Tel. Feltham 6591/4

CHIMNEY LININGS THAT LAST



C.E.A. Bow generating station chimney lining gunited with refractory concrete

Chimney stacks lined with steel, Portland cement concrete or ordinary brick-work mortar are seriously affected by corrosion caused by heat, condensation, acidity or sulphurous combustion gases. To prevent such deterioration, it is now standard practice to line chimneys with Ciment Fondu mortar, because of its high resistance to dilute sulphur acids and sulphates, and its ability to provide a strong bond even at a temperature well above that of the hottest stack.

The best means of providing adequate protection is to apply Ciment Fondu with a pneumatic "gun" directly against the steel shell or structural Portland cement concrete.

Up to 300°—350° C ordinary concreting sands can be used, but for higher temperatures a refractory aggregate (e.g. crushed firebrick or crushed insulating brick) should be employed.

For more information, send for our booklet "SHOOTING" STACK AND FLUE LININGS WITH ALUMINOUS CEMENT MORTARS.



The Cement for Industry

FOR SPEED · STRENGTH · RESISTANCE · REFRACTORINESS

Manufactured by:

LAFARGE ALUMINOUS CEMENT CO. LTD, 73 Brook St, London, W.1. Tel. MAYfair 9546

AP 113

STELMO

LIMITED

announce their


NEW ADDRESS

**WESTWELL LEACON,
CHARING, ASHFORD,
KENT.**

TELEPHONE: CHARING 395-7

This new and up-to-date works, with its greater design-department facilities, will enable us to meet the ever-increasing demand for the specialised STELMO products and services so well known throughout the world.

Multi-wire strand For prestressed concrete



This photograph shows the stressing of multi-wire "Bridge" Strand at the Perth Narrows Bridge in Australia. "Bridge" Strand is made from Somerset Wire.

CONSULTING ENGINEERS: G. Maunsell & Partners
PRESTRESSED CONCRETE CONSULTANT: E. W. H. Gifford
CONTRACTORS: Christiani & Nielsen Ltd.

**IF YOU WANT TO PUT STEEL INTO CONCRETE
GET IN TOUCH WITH**

G.K.N. Reinforcements Ltd

197 KNIGHTSBRIDGE, LONDON, S.W.7. KENSington 6311

SMETHWICK, BIRMINGHAM (Smethwick 1991) • MANCHESTER (Ardwick 1691)
GLASGOW (Bell 2444) • MIDDLESBROUGH (3843) • CARDIFF (Cardiff 45220)
BRISTOL (Bristol 21555) • LEICESTER (Leicester 25114) • LEEDS (Leeds 27311)

WORKS AT CARDIFF, SMETHWICK, WIGAN & GLASGOW

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 5d. a word: minimum, 12s. Situations Vacant, 6d. a word: minimum, 15s. Other miscellaneous advertisements, 6d. a word: minimum, 15s. Displayed advertisements, 40s. per column inch. Box number 1s. extra.

Advertisements must reach this office, 14 Dartmouth Street, London, S.W.1 by the 23rd of the month preceding publication.

SITUATIONS VACANT.

SITUATIONS VACANT. Senior and intermediate designer-draftsmen, experienced in reinforced concrete, required. Excellent opportunities in an expanding organisation for the right men. Positions are eventually pensionable, and offer first-class experience. Apply in writing to CLARKE, NICHOLLS & MARCEL, consulting structural engineers, Berkeley Cottage, Berkeley Square, Bristol, 8.

SITUATIONS VACANT. Reinforced concrete detailers, all grades, required for new office opening in Bournemouth. Good conditions, five-days' week, salaries according to capabilities. Interviews: London and Bournemouth. Details, with present salary, to Box 4623, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Consulting engineers have vacancies for reinforced concrete detailers, and designer-draftsmen. Salaries in accordance with experience. Luncheon vouchers. Apply in writing to BYLANDER, WADDELL & PARTNERS, 169 Wembley Park Drive, Wembley, Middlesex.

SITUATIONS VACANT. Reinforced concrete designer and detailers required for South London consulting engineer's office. Good salaries and prospects. Telephone Tate Gallery 8496.

SITUATIONS VACANT. Detailer and designer-draftsmen required for rapidly expanding reinforced concrete design office. Permanent superannuated positions. Five-days' week. Excellent working conditions in modern offices with canteen. Write, stating experience, age, and salary required, to THE SECRETARY, THE ROM RIVER CO. LTD., 100 Stewarts Road, Battersea, London, S.W.8.

SITUATIONS VACANT. Designer-detailers required for permanent positions with opportunity to also assist on prestressed concrete design. Previous experience in reinforced concrete necessary. Work involves occasional site visits and scope for improving position, and widening experience. Telephone Victoria 4287 for appointment, or write DONOVAN H. LEE, Consulting Engineer, 66 Victoria Street, London, S.W.1.

SITUATIONS VACANT. Assistant engineers, steelwork designer-draftsmen, reinforced concrete designer-draftsmen, and detailer-draftsmen required for varied and interesting work on structures for industrial, commercial, medical, and residential buildings. Five-days' week. Luncheon vouchers. Apply, with details of experience, and salary required, to JOHN F. FARQUHARSON & PARTNERS, Chartered Structural Engineers, 34 Queen Anne Street, London, W.1. Telephone Langham 6081.

SITUATIONS VACANT. E. J. COOK & CO. (ENGINEERS) LTD. require five reinforced concrete designer-detailers for expanding design office. Not less than ten years' experience H.N.C. or similar level. Salaries £800-£1200 per annum according to experience and ability. Five-days' week. Luncheon vouchers. Superannuation scheme after twelve months' service. Application forms from 54 South Side Clapham Common, London, S.W.4 (Macaulay 5522).

FULLY QUALIFIED STRUCTURAL ENGINEER

with wide experience for position as CHIEF ENGINEER in reinforced and prestressed concrete and structural steelwork (including bridges), required by Consulting Engineers, Westminster. Prospects of partnership interest in firm. Write in confidence, stating age and full details of experience and qualifications. Box 4595, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

JOHN LAING AND SON LIMITED

require

SITE AGENTS

for senior appointments on large construction contracts in various parts of the country. Applicants will be required to have sound experience on a wide variety of contract work. L.I.O.B. or A.M.I.C.E. qualifications preferred. Age 30-40. Full mobility essential. Salary commensurate with experience and qualifications.

Successful applicants who prove themselves may expect advancement and permanent pensioned employment.

Apply in writing to PERSONNEL MANAGER (SA5), JOHN LAING AND SON LIMITED, Mill Hill, London, N.W.7.

BRC
**Experienced
Reinforced
Concrete
Designer/Detailers
and Draughtsmen
Wanted
For our London &
Provincial Design
Offices**

Apply

Chief Engineer: A. P. MASON,
B.Sc., M.I.C.E., M.I.Struct.E., M.ASCE.
THE BRITISH REINFORCED CONCRETE
ENGINEERING CO. LTD., STAFFORD

SENIOR DESIGN DRAUGHTSMEN AND ENGINEERS TO WORK ON THE OPERATIONAL LAUNCHER FOR BLUE STREAK

Long-Range Ballistic Missile

Candidates must have a good practical background and experience in any of the following:

- medium structural engineering
- chemical, refinery or process plant layout and pipework
- electrical control systems and installations associated with chemical, refinery or process plant.

Draughtsmen should have at least ONC, and engineers appropriate professional qualifications.

All appointments will be in our London Offices.

Applications, in confidence, should be addressed to:

**The Personnel Manager (Ref. 53)
DE HAVILLAND PROPELLERS
LIMITED**

37/39 John Street, Theobalds Road, London W.C.1

SITUATION VACANT. Structural engineer with experience of reinforced concrete and/or structural steelwork required by consultants. Interesting work consisting of research into and development of new structural techniques, and the use of new materials as well as traditional construction. Box 4627, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. A small firm of consulting engineers in West End requires one senior designer and a number of designer-detailers. Very good prospects. Bonus payable twice a year. Only first-class men need apply to Box 4628, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. NUCLEAR CIVIL CONSTRUCTORS require in their London office well-experienced reinforced concrete designers for work on nuclear power stations. Apply in writing to the CHIEF ENGINEER, 32 Carnaby Street, London, W.1, giving all relevant details.

SITUATIONS VACANT. Consulting engineers require senior and intermediate detailers in reinforced and prestressed concrete, experienced in multi-story buildings. Interesting work with good prospects for the right men. Luncheon vouchers. No Saturdays. Apply to CHAMBERLAIN & PARTNER, 29/30 Bedford Row, London, W.C.1, or telephone Chancery 8248-9.

SITUATION VACANT. Concrete engineer, Durban, seeks London opposite number to exchange homes and take position in firm for a year from early 1960. Salary £1200. At least four years' qualified experience necessary. Write immediately to Box 2083, Durban, South Africa.

SITUATIONS VACANT. JENKINS & POTTER have vacancies for senior and junior structural assistants. Degree or Higher National and some reinforced concrete experience essential, but steelwork and timber experience appreciated. 12-14 Great Turnstile, Lincoln's Inn Fields, London, W.C.1. Telephone: Holborn 1291.

SITUATION VACANT. MIDDLESEX COUNTY COUNCIL. Structural Engineering assistant Apt. 111 (£910-£1095 per annum) with at least three years' experience in designing and detailing reinforced concrete and structural steelwork necessary. Established and pensionable, prescribed conditions. Forms from COUNTY ARCHITECT (s.a. f'scap e.) 1 Queen Anne's Gate Buildings, Dartmouth Street, London, S.W.1, not later than 31 December. (Quote B.475, C. & C.E.)

SITUATIONS VACANT. Structural designers and draughtsmen, with a minimum of two years' experience after gaining Higher National or equivalent, required by consulting engineers. Five-days' week. Luncheon vouchers. Salary £700 to £1000 depending on qualifications and experience. Apply in writing, with full details, to ANDREWS, KENT & STONE, 60 Wardour Street, London, W.1.

SITUATION VACANT. Senior engineer required for London professional office. Must have professional qualifications, preferably degree, and at least five years' design experience in structural reinforced concrete. Knowledge of steelwork an advantage. Age limits 30-40. Candidates should have site experience, and be capable of handling contracts from start to finish. The work is varied and offers scope for initiative. A good salary will be offered. Apply, stating experience, and salary required, to FARMER & DARE, Romney House, Tufton Street, Westminster, S.W.1.

SITUATIONS VACANT. Consulting engineers engaged on a variety of structural design projects at home and overseas require experienced assistants for their London office. Five-days' week and luncheon vouchers. Apply, giving details of age, qualifications and experience, in writing, to MAURICE NACHSHEN & PARTNERS, 58 Victoria Street, London, S.W.1.

REINFORCED CONCRETE and STEELWORK DESIGNERS and DETAILERS

required to work at St. Albans Head Office on a wide variety of building frames and industrial structures.

Permanent positions. Good salaries. 5-days' week. Staff Pension Scheme.

Telephone St. Albans 56011 Ext. 19 or write, stating age and experience, to
OSCAR FABER & PARTNERS (Dept. F).
47 Holywell Hill, St. Albans, Herts.

GOVERNMENT OF THE FEDERATION OF RHODESIA AND NYASALAND VACANCY : ASSISTANT STRUCTURAL ENGINEER : MINISTRY OF WORKS

Applicants must be Corporate Members of the Institution of Civil and/or Structural Engineers, or hold a degree in Engineering with a minimum, in the latter instance, of four years' post-qualification experience.

Applicants must have a sound knowledge of reinforced concrete design and detailing; some experience of steel structure is desirable.

Duties in the main consist of preparing design and details of reinforced concrete frames for Government buildings.

The commencing salary for a person holding one of the above qualifications and having four years' relevant experience will be £1,300 p.a., rising by yearly increments of £50 to £1,650 p.a.

Application forms and further details from the Secretary (R), Rhodesia House, 429 Strand, London, W.C.2.

SITUATION WANTED.

SITUATION WANTED. Structural engineer, 30, B.Sc. with eight years' drawing office and site experience in in-situ and precast reinforced concrete, used to acting on own initiative and to carrying considerable responsibility seeks senior position in London area where technical qualifications and experience can both be used to advantage. Good knowledge of languages. Box 4629, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.


FOR SALE, WANTED OR HIRE.

FOR SALE. 500 tons 3-station concrete slab press, suitable for slabs up to 36 in. x 24 in., and kerbs. Self-contained oil pump unit. Unused. Box 4626, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FOR SALE. Steel fencing stakes, chain link, etc. L. STEPHENS & SON LTD., Bath Street, London, E.C.1. Telephone Clerkenwell 1731.

FOR HIRE. Lattice steel erection masts (light and heavy), 30 ft. to 150 ft. high, for immediate hire. BRIDGMAN, 21 Hobart House, Grosvenor Place, London, S.W.1.

WANTED. Regularly. Round M.S. reinforcing bar of cuts. Minimum lengths 2 ft. Also surplus parcels of reinforcement. H. & J. R. SAUNDERS & CO. LTD., Hainault Road, Leytonstone, London, E.11. Leystone 4383.



Trent Gravels 10,000 tons per week

Washed & Crushed 1½ in. to ½ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

Telephone: Beaton 54255

NOTTS

1959.

ERA-
ID

R :
S

s of the
neers, or
minimum,
-qualifi-

ledge of
; some
g design
mes for

holding
ing four
oo p.a.,
650 p.a.
rom the
Strand,

r, 30, B.Sc.
experience of
to acting as
responsibility
nical qualifi-
advantage
CONCRETE AND
outh Street

E.
slab pres.
kerbs. Sol-
S, CONCRETE
outh Street

ak, etc. E.
don, E.C.1

(light and
hire Bell-
don, S.W.1
ing bar of
reels of rod
oad, Leyton

LINCOLN
NEWARK

GRANTHAM

MILTON
MORLEY

els
week

1/4 in.

concrete
Prompt
ve prices
es.

LTD
NOTTS



Practising
at
the Bar



Pleading the case for Tentor Bar has its advantages; it has a clean record; it reinforces concrete extremely well, and is delivered promptly from six different places. Tentor Bars for concrete reinforcement set high standards in tensile and bond strength, save up to 15% of the cost of Plain Rounds, require no hooks, and can be supplied to meet contract requirements, cut or bent to specification, in sizes from $\frac{1}{4}$ " to $1\frac{1}{4}$ "

TENTOR BARS
are delivered promptly
from
CARDIFF. LONDON.
WIGAN. SMETHWICK.
STAFFORD & SHEFFIELD

Technical enquiries to:

The Tentor Bar Company Ltd.
197 Knightsbridge, London,
S.W.7. Telephone:
KENsington 6311. Telegrams:
TENTORED, London, S.W.7

Tentor Bars are supplied by the following companies and their branch offices:—

B.R.C. STEEL LTD.,
Silkmore Lane, Stafford. Stafford 444
G.K.N. REINFORCEMENTS LTD.,
197 Knightsbridge, London, S.W.7. KENsington 6311
McCALL & CO. (SHEFFIELD) LTD.,
P.O. Box 41, Sheffield. Rotherham 2076
STEEL, PEECH & TOZER, LTD.,
Branch of The United Steel Companies Ltd.,
The Ickles, Sheffield. Sheffield 41011

TENTOR BARS Registered Trade Mark

GLASGOW

NEWCASTLE

BELFAST

LEEDS

LIVERPOOL

MANCHESTER

DUBLIN

LEICESTER

STAFFORD

BIRMINGHAM

CARDIFF

BRISTOL

LONDON

BRC

Specialists in Reinforced Concrete Design and Suppliers of Reinforcement, with Design and Branch Offices strategically placed throughout the British Isles

Within the BRC design service there is a Site Investigation Department

**REINFORCED CONCRETE IS
CONSTRUCTION AT ITS BEST**

There are vacancies for experienced engineers in several of our design offices.

The British Reinforced Concrete Engineering Co. Ltd., Head Office & Works: Stafford

8930

M-W. 8793

CEMBER, 1993

Stafford

M-W 8798

ehall 4581